

CONCRETE AND CONSTRUCTIONAL ENGINEERING

INCLUDING PRESTRESSED CONCRETE

AUGUST, 1955.



Vol. L, No. 8

FIFTIETH YEAR OF PUBLICATION

PRICE 1s. 6d.

ANNUAL SUBSCRIPTION 18s., POST FREE. 83/90 in Canada and U.S.A.

LEADING CONTENTS

	PAGE
Liberal Education in a Technical Age	281
Design of Non-Prismatic Members. <i>By H. P. Vasuani, B.Eng., D.I.C.</i>	283
The late Professor Gustave Magnel	287
Book Reviews	288
A New Method of Prestressing Circular Reservoirs	289
Bending and Axial Stresses in Circular Columns. <i>By R. J. Bartlett</i>	293
A Prestressed Bridge in the U.S.A.	298
Tests on Lightweight Prestressed Beams	301
Eccentrically-loaded Columns	303

No. 973.

ISSUED MONTHLY

Registered for
Canadian Magazine Post

BOOKS ON CONCRETE

For catalogue of "Concrete Series" books on concrete and allied subjects, send a postcard to:

CONCRETE PUBLICATIONS LTD., 14 DARTMOUTH ST., LONDON, S.W.1

After five years



These illustrations are of 12in. x 6in. concrete cylinders, mixed 4-2-1 with water/cement ratio of 0.6 made to Code of Practice. For the left-hand cylinder in each case ordinary Portland Cement was used and for the right-hand cylinder, Sulphate-Resisting Cement. The cylinders in A were immersed in magnesium sulphate solution where the equivalent SO_3 content is 500 parts per 100,000. The cylinders shown in B were immersed in a sodium sulphate solution of similar SO_3 content. The photographs were taken after the cylinders had been immersed for five years. The value of using Sulphate-Resisting Cement for concrete work which is liable to the destructive action of soluble sulphates is clearly indicated since on the majority of sites the sulphate concentration seldom exceeds the equivalent SO_3 content of the solution used for the test.

SULPHATE-RESISTING CEMENT



Full details will be sent on application to

THE CEMENT MARKETING COMPANY LIMITED

PORTLAND HOUSE, TOTHILL STREET, WESTMINSTER, LONDON, S.W. 1.

OR G. & T. EARLE LTD. HULL

THE SOUTH WALES PORTLAND CEMENT & LIME CO. LTD. PENARTH, GLAMORGAN

British Cement is the Cheapest in the world

S.R.C.4

PROMETO MOVING FORMS

for
monolithic
concrete
construction


**a rapid and highly economical method
of erecting structures of all kinds**

PROMETO hydraulically controlled moving-forms and equipment enable a high rate of construction to be maintained with minimum labour requirements. They provide the means of making substantial savings in the cost of erecting Silos, Chimneys, Water Towers, Multi-Storey Flats, the lining of Mine and similar shafts, Elevator Houses, and many other types of concrete structures. We have the sole rights for the manufacture and use of PROMETO equipment in the United Kingdom, and are prepared to enter into sub-licence arrangements with selected Contractors for individual jobs or prescribed districts. Inquiries are invited from Consulting Engineers, Architects and Contractors.

WILLIAM THORNTON & SONS LTD
WELLINGTON ROAD
LIVERPOOL


Building and Civil Engineering Contractors

for
bars
from
 $\frac{1}{4}$ " to 2"
dia.



BAR-BENDING

with accuracy·speed·economy



**ARD-50
MODEL**

**ELECTRIC
OR
ENGINE DRIVEN**

The ARD-50 Model, illustrated above, has an automatic control which permits the desired bending angle to be pre-set, greatly facilitating repetition bending. The bottom illustration shows the bending of an angle loop in one operation. This model is also fitted with a backrest for multiple bending of small diameter bars. We also supply, at extra cost, a special device for bending Hoops and Spirals, and formers and backrests for special steel such as "Square Grip," "Twistee," and "Tentor," etc. This model is complete with standard accessories for bends on a 4D basis, and can be fitted with Electric motor, Air-cooled Petrol engine or Air- or Water-cooled Diesel engine. Our range of bending equipment also includes the RAS40 model for bending bars up to $1\frac{1}{2}$ in. diameter. Both models are available for sale or hire. Full details will be sent on request.


CEMENT & STEEL, LTD., SECOND AVENUE, CHATHAM, KENT.

Telephone : Chatham 45580.

Telegrams & Cables : Cembelgi, Chatham.

FEBCRETE

air entrained concrete



There is indisputable evidence that "Febcrete" Air Entraining Agent provides an easy means of producing better concrete with all-round savings in cement requirements and concrete-placing costs which are far greater than the infinitesimal cost of "Febcrete." This evidence, which is based on the use of "Febcrete" on important concrete constructional undertakings throughout the world, is available without obligation to all Engineers and Contractors.

FEB (GREAT BRITAIN) LTD.

LONDON: 102 KENSINGTON HIGH STREET, W.8.

MANCHESTER: ALBANY WORKS, ALBANY ROAD, CHORLTON-CUM-HARDY

Telephone: Western 0444

Telephone: Chorlton 1063



NEEDLE VIBRATOR

with one-inch
diameter head
for concrete
which is congested
with reinforcement
or prestressing wire

Our range of immersion vibrators also includes the Giant pneumatic vibrator with a 4-in. head, the General-Purpose pneumatic vibrator with a 2½-in. head, and the Lightweight electric vibrator with heads ranging from 1½ in. to 3 in. diameters, which is also available with petrol engine.

COMPACTORS ENGINEERING LTD.


65 EFFRA ROAD,

LONDON, S.W.2

TELEPHONE : BRIXTON 4081-3

This one-inch head pneumatic immersion vibrator solves all problems in obtaining efficient vibration of thin concrete members and concrete which is congested with reinforcement or prestressing wire. The vibrator will give equal satisfaction for general concrete work, as the 1" dia. head can be interchanged in a few minutes for a more powerful 1½" or 2½" dia. head. The weight of the type AS 30 is only 15 lb. and its frequency is 12,000 r.p.m.

**APPROVED
FOR SITE TESTING**
on all Government Departments' Contracts



4" PRESS AND MOULD

6" PRESS AND MOULD

in use all over the world

**MILBANK-WELLS HYDRAULIC PRESS AND CUBE MOULDS
FOR CONCRETE TESTING**

Presses and Moulds in the 2 sizes for Testing 4 in. and 6 in. cubes
up to 16,000 lb. per square inch, complying with B.S. 1881.


MILBANK FLOORS LTD.

PRESTRESSED CONCRETE CONSTRUCTION

RIVER HOUSE, EARLS COLNE, ESSEX.

Telephone: Earls Colne 410

Manufactured for us by Horner & Wells, Ltd., Engineers, Chelmsford, Essex.

ONE...**TWO!**

'STABIL' BINDERS

ARE GREAT LABOUR SAVERS


In one simple action they fix reinforcing rods as though welded. No slipping. No "fiddling" with wire. No tools to get mislaid. Any workman can use them. Made in all sizes for binding $\frac{1}{4}$ -inch up to $1\frac{1}{4}$ -inch rods. Give "Stabil" Binders a trial and judge for yourself.

- SEND TO-DAY for demonstration samples and prices.

HUNTLEY & SPARKS LTD

DE BURG RD., S. WIMBLEDON, S.W.19

Phone: Liberty 2446



Trent Gravels

10,000 tons per week

Washed & Crushed $1\frac{1}{2}$ in. to $\frac{1}{4}$ in.

We are the leading suppliers of high-class concrete aggregates in the area shown above. Prompt deliveries guaranteed and keen competitive prices quoted. Send for samples and prices.

TRENT GRAVELS LTD

ATTENBOROUGH

NOTTS

Telephone: Beeston 54255.

"CONCRETE SERIES"


BOOKS ON CONCRETE

These well-known books deal with practically every aspect of the design and construction of reinforced concrete and precast concrete, the manufacture and chemistry of cement, and kindred subjects. For a complete catalogue giving prices in sterling and dollars, send a postcard to :

CONCRETE PUBLICATIONS, Ltd.

14 Dartmouth St., London, S.W.1

England



*For faster placing
and better concrete
use the*



HUMDINGER

IMMERSION VIBRATOR

AVAILABLE WITH GRINDING ATTACHMENTS



Here is an immersion vibrator that will cut your concrete-placing costs in a half-dozen ways. High vibrating frequencies of up to 12,000 r.p.m. give stronger concrete and speed up placing—and you can strike shuttering sooner. At the same time, the 'Humdinger' flexible shafts operate at **QUARTER SPEED!**

And this means longer life and less maintenance—the drives just keep on running week after week.

Plant records prove that contractors and civil engineers are changing to 'Humdinger' after seeing the difference they can make in concrete placing. Prove it for yourself by using one on your next vibrating job. You can have a 'Humdinger' on trial or hire (with option).




PETROL AND ELECTRIC MODELS AVAILABLE

ACE MACHINERY LIMITED

VIBRATOR DEPT., PORDEN ROAD, BRIXTON, LONDON, S.W.2 Telephone: BRIXton 3293 (9 lines)

Buy  *and you buy* **RELIABILITY**

"CAPCO" H. F. VIBRATOR



for compacting mortar cubes for Compression Test B.S. 12/1947, B.S. 915/1947, B.S. 146/1947, B.S. 1370/1947. New type automatic control—optional. The vibrator illustrated in the B.S. was built in our works.

The "CAPCO" range of concrete testing apparatus also includes Cube Moulds; Slump Cones; Tensile, Vicat, and Cylindrical Moulds; Tile Abrasion Machines; Compacting Factor Apparatus.

Full details on request.

CAPCO (SALES), LTD.

BEACONSFIELD ROAD, LONDON, N.W.18.

Telephone: WILLESDEN 9067-8. Cable: CAPLINKO, LONDON

(Sole Agents for all

"Capco" Products)



PIN YOUR FAITH
TO THE TESTED
BRAND.

THIS LABEL ON
EVERY BARREL
CARRIES WITH IT
FORTY YEARS'
EXPERIENCE OF
MANUFACTURE.

NONE OTHER IS
"JUST AS GOOD"

THE LEEDS OIL & GREASE CO.

Phone 22480

LEEDS, 10

'Grams: "Grease."



PILING

We have a range of the most up-to-date piling plants in this country capable of handling reinforced concrete piles up to 95 ft. in length and 13 tons in weight. To drive the piles steam hammers are used of which the largest weigh 61 tons.

Several of these plants are power driven in every motion, can rotate to face in any direction, and are particularly suited to drive raking piles as they can vary their batter from 1 in 24 backward to 1 in 6 forward.

When mounted on travelling undercarriages up to 150 ft. in length our piling plants can operate over large areas with speed and efficiency.

PETER LIND & CO LTD

ROMNEY HOUSE, TUFTON STREET, LONDON, S.W.1

TELEPHONE ABBEY 7361



*Candy Filter House for South-West Suburban Water Company
Mr. H. Austin Palmer, Engineer*

THE BEST WAY to illustrate CONCRETE
is by HALF-TONE BLOCKS
OF THE HIGHEST QUALITY

Complete Service of
ENGRAVING, TYPESETTING,
PHOTOGRAPHY,
ELECTROTYPING and STEREO-
TYPING and ARTISTS' WORK


THE STRAND ENGRAVING COMPANY LIMITED
8 & 9 ESSEX STREET, STRAND, W.C.2

Telephone: Temple Bar 6311

Engravers to "Concrete"



● Reproduction by courtesy of Poplar Borough Council, Percy Biton Limited (General Building Contractor) and Scaffolding (Great Britain) Ltd.



Helping to Rebuild Poplar

SCAFFOLDING (GREAT BRITAIN) LTD., chose THAMESPLY Phenol Bonded Plywood Shuttering to form the internal and external walls of flats on Poplar Borough Council's Teviot Street Estate.

Thamesply shuttering is lightweight and quickly erected. It must withstand the British Standard 72-hour boiling test, and with reasonable care upwards of 80 uses can be obtained.



PLYWOOD SHUTTERING

(Phenol Bonded "W.B.P." Test) • W.B.P. means Water and Boil Proof

Supplied only through the usual trade channels

THAMES PLYWOOD MANUFACTURERS LTD

Harts Lane • Barking • Essex • Telephone: Rippleway 5511

YAS205

GUNITE SPECIALISTS

**W.M. MULCASTER
& CO. (CONTRACTORS) LTD.**

We invite inquiries for Gunite Linings and Renderings
for new or old structures of every kind in any part
of the country.

HASLINGTON

Telephone: Crewe 2265-6.

CREWE



THE "JOHN BULL" CONCRETE BREAKER

NEW "B.A.L." TYPE.

INCREASED:—

PENETRATION, RELIABILITY, LIFE.

REDUCED:—

VIBRATION, NOISE AND WEAR.

THESE ARE THE SALIENT FEATURES
OF THE NEW CONCRETE BREAKER

★ ★ ★

REAVELL & CO., LTD.


RANELAGH WORKS, IPSWICH.

TELEGRAMS: "REAVELL, IPSWICH."

TELEPHONE: 2124

Christiani & Nielsen Ltd.

CIVIL ENGINEERING CONTRACTORS



RECENTLY COMPLETED FOUR-STORY HOP WAREHOUSE


at Paddock Wood, Kent, for the
HOP MARKETING BOARD

Architects : MESSRS. FAIRTLOUGH & MORRIS, FF.R.I.B.A.
Designers of Concrete Structure : MESSRS. R. E. EAGAN, LTD.
Main Contractors : MESSRS. HALSE & SONS, LTD.

ROMNEY HOUSE, TUFTON STREET, WESTMINSTER
LONDON S.W.1

Tel. : ABBey 6614/7

Tel. Address : RECONCRET SOWEST LONDON



An Electrically Driven PC4 Concrete Pump.
Capacities from 8 to 10 cu. yds. per hour.
Ranges actually obtained 125 ft. vertical or
1,500 ft. horizontal.

FOR SALE AND HIRE

EFFICIENT RECONDITIONING SERVICE

CONCRETE BY PUMP AND PIPELINE

- The latest and most efficient method of placing concrete.
- Life of Pump practically indefinite: all essential surfaces in contact with concrete are renewable.
- Pumpable concrete must of necessity be good concrete.
- Pump and Mixing Plant can be located at the most convenient position within the pumping range.
- The continuous output of the Pump at a constant speed governs the working of the whole concreting gang.

THE REGISTERED TRADE MARK OF

PUMPCRET

THE CONCRETE PUMP COMPANY LIMITED

THE CONCRETE PUMP COMPANY LTD

4 STAFFORD TERRACE, LONDON, W.8

Telephone: Western 3546

Telegrams: Pumpcret, Kens, London

CEMENTATION



If you've a problem
of this kind—consult

The **C**EMENTATION
COMPANY LIMITED

BENTLEY WORKS, DONCASTER. Telephone: Doncaster 54177-8-9



no primer
needed

evodyne chlorinated rubber paint



needs no

primer on surfaces of low porosity



such as asbestos, cement

and concrete; it is acid-resistant



impermeable



unaffected by alkalis and



corrosive gases.



EVODE LIMITED • GLOVER STREET • STAFFORD

Telephone: 1980/1/2 Telegrams: Evode, Stafford

LONDON OFFICE: 1 VICTORIA STREET, S.W. 1 Telephone: Abbey 0022/3

EVODYNE
CHLORINATED RUBBER
PAINTS

37



**PRESTRESSED
CONCRETE UNITS
FORMING
TRUNK ROAD BRIDGE**

Photograph by
permission of
Lincolnshire
C.C.

**ANOTHER
ANGLIAN
PRESTRESSED PRODUCT**


**PYLONS · PILES AND
SHEET PILES · ROAD
AND RAIL BRIDGES
ROOF & FLOOR BEAMS**

ANGLIAN BUILDING PRODUCTS LTD · LENWADE 15 · NORWICH

Tel.
Gt. Witchingham 291

REINFORCED CONCRETE ROADS

ECONOMIC
EFFICIENT
ENDURING



McCall's
MATOBAR
Welded
FABRIC REINFORCEMENT

McCALL & COMPANY (SHEFFIELD) LIMITED
TEMPLEBOROUGH, SHEFFIELD, P.O. BOX 41 Telephone: ROTHERHAM 2076 (8 lines)
and at 8/10, GROSVENOR GARDENS, LONDON S.W.1 Telephone: SLOANE 0428



MODERN METHODS Bulk handling of cement in conjunction with concrete weigh-batching plant and tower cranes are now taking the place of older methods. More of our contracts are being equipped in this way.

RUSH & TOMPKINS LTD.

Building and Civil Engineering Contractors

SIDCUP • LONDON • DURBAN • COLOMBO • EDMONTON, ALBERTA



A symbol of quality materials, experienced workmanship, expert supervision, and excellent service.

for all forms of **PRECAST CONCRETE**

We specialise in the production of Precast Concrete structural members to standard or special designs, also products for the Electrical Industry, Sports Ground Contractors, and Fencing Contractors, and shall be pleased to submit quotations for your requirements.

H.B. CONCRETE CO. LTD.

Head Office and Works: VICARAGE ROAD, EGHAM, SURREY. Telephone: Egham 3092



**DELIVERED DIRECT TO ANY
CONTRACT BY MOTOR LORRY.**

Quotations on Application.

Telephone: Paddington 2924 (3 lines).

**WASHED
BALLAST, SAND, SHINGLE &
Crushed Aggregate for Reinforced Concrete.**

WILLIAM BOYER & SONS, LTD.

Sand and Ballast Specialists,

**IRONGATE WHARF,
PADDINGTON BASIN, W.**

MEMBERS OF B.S. & A.T.A.

BARS for REINFORCEMENT

BARS in sizes from $\frac{3}{8}$ in. to $1\frac{1}{2}$ in. Mild Steel 28/33 tons Tensile cut to lengths.

BARS bent to schedule.

BARS for prompt delivery to site at competitive prices.

Send your inquiries to

PASHLEY & TRICKETT · LTD.

STOKE STREET, SHEFFIELD, 9. Telephone: 41136-7. Telegrams: "PET" SHEFFIELD, 9

use the **A.B.** **SERVICE** **for concrete work**

SHUTTER PANELS

All sizes and types

ADJUSTABLE SHORES

for floor and beam support

ADJUSTABLE CENTRE FORMS

for floor support

SHUTTERLOCK WALING CLIPS

for bracing with scaffold tube and locking the panels together, eliminating nuts and bolts in shuttering. Tremendous saving in erecting and striking costs

COLUMN CLAMPS : BEAM CLAMPS

ROAD FORMS : TRENCH STRUTS

We also design and manufacture Steel Moulds for Floor Beams, Piles, Railway Sleepers and all other precast concrete products

Let us solve your problems

A. B. MOULD & CONSTRUCTION CO., LTD.

92 WHITEHORSE ROAD

CROYDON

SURREY

Telephone : Thornton Heath 4947.

Telegrams : Abmould, Croydon.

WORKS: VULCAN WAY, NEW ADDINGTON, SURREY

GLASCRETE for SHELL ROOFS

Shell roofs can be efficiently lighted by simply placing precast GLASCRETE panels on the shuttering and casting in monolithic with the roof, thus saving time and labour in trimming openings.

Panels are cast to the curve of the roof and anchor bars are left protruding from the frame for bonding to the roof slab.



Factory, London.

Architects : Messrs. Clifford Tee & Gale.

Telephone: CEN. 5866
(5 lines)

J. A. KING & CO. LTD.,
181, QUEEN VICTORIA ST., LONDON, E.C.4

**CONCRETE
PROOFING
Co. LTD.**

**GUNITE
SPECIALISTS**

Expert advice and schemes submitted for gunite work of every kind. Complete information on the various uses of gunite will be gladly sent on request.

96, Victoria Street, Westminster, S.W.1

Telephone:
VICTORIA 7877 and 9278



Anywhere on earth...

Here on this barren stretch of the desolate "Skeleton Coast" in South West Africa, among rocky hills and dunes whipped into grotesque shapes by the corrosive blast of winds charged with salt and sand, diamonds are mined literally on the sea shore; and wherever men can work, so can the Land-Rover. A mobile or stationary power unit, a load or passenger-carrier, going anywherepulling anything, the 4-wheel drive Land-Rover can take it. All over the world, the Land-Rover stands for mobility, endurance, toughness.

... **LAND** →
← **ROVER** can take it

REINFORCED
CONCRETE
by



Reinforced Concrete Road Bridge at Wool, for Dorset C.C. J. J. Leeming, M.I.C.E., County Surveyor

A. G. MANSELL & CO. LTD

CIVIL ENGINEERING AND BUILDING CONTRACTORS

BRIDGES - RIVER AND SEA DEFENCE WORKS - WATER TOWERS - BUNKERS
SILOS - INDUSTRIAL BUILDINGS - ROADS - FOUNDATIONS - AND PILING.

70 VICTORIA STREET, LONDON, S.W.1. Telephone: TATE GALLERY 0088

COPPER STRIPS

for expansion joints


All Reinforced Concrete Engineers recognise the advantages of using copper strips for sealing joints in concrete work. Copper is ductile, will not crack under repeated bending, is non-corrosive and is unaffected by wet concrete. We specialise in the supply of perforated copper strips of all required lengths and widths for expansion joints, and shall be pleased to submit prices against detailed specification.



ALEX J. CHEETHAM LTD.

MORTON STREET · FAIRFORTH · MANCHESTER
Telephone: FAIRfworth 1115/6

DS14



McCall's "Macalloy"
Prestressing Steel
 for
South Eastern Gas Board's
new premises at Greenwich

Precast Arch-Ribs — Lee-McCall post-tensioned units

The photograph shows a new sulphate of ammonia store and bagging house for South Eastern Gas Board at Phoenix Wharf, Greenwich.

Designed by The Central Construction Department of the South Eastern Gas Board in conjunction with "Twistell" Reinforcement Limited.

Contractors : Demolition & Construction Co. Limited.

Precast End Blocks : Liverpool Artificial Stone Company.

Precast Cladding Slabs : Anglian Building Products Limited.

McCALLS MACALLOY LIMITED

TEMPLEBOROUGH • SHEFFIELD • P.O. BOX 41









Phone: ROTHERHAM 2076 (P.B. EX 8 Lines). LONDON OFFICE: 8-10 GROSVENOR GARDENS, S.W.1. Tel: Sloane 0428

See for Yourself

The TIME and LABOUR SAVED by

'MULTIBLOC'

Handling Equipment

OLD METHODS Using Pallets	MULTIBLOC Without Pallets
MAKING AREA 	MAKING AREA  12 BLOCKS PER DROP
BLOCKS MOVED TO STORAGE SITE LOADED 1 AT A TIME 	BLOCKS MOVED TO STORAGE SITE PATENT TRUCK LIFTS ONE COMPLETE DROP OF 12 
STORAGE SITE  STACKED 1 AT A TIME	STORAGE SITE  GRAB STACKS 3 DROPS OF 12 AT 1 LIFT
LOADING  LOADING 1 AT A TIME	LOADING  GRAB LOADS 4 DROPS OF 12 AT A TIME (72 BLOCKS)

"Multibloc" Handling is a streamlined system of producing better building blocks, and moving them with minimum breakages, faster and with less labour, at a lower capital outlay than has hitherto been possible.

* In the example given the "Multibloc" machine is making 4-in. blocks. When other sizes are made, the number produced at one drop varies proportionately.

"MULTIBLOC" HANDLING EQUIPMENT INCLUDES :

- "Multibloc" Aggregate Feed Trucks
- "Multibloc" Block Making Machine
- "Multibloc" Patent Lift Trucks
- "Multibloc" Grab and Gantry



Let us explain, without obligation, how this flexible "Multibloc" system can be applied to your own particular problems.

Sole Concessionaires for the British Isles

ALAN R
DAVIES of BRISTOL

Contractors' and Quarry Plant

20 WHITELADIES ROAD,
BRISTOL, 8

Telephone :
38418/9

Telegrams :
"Alanar, Bristol, 8

Steel Reinforcement

. . . bent . . . bundled . . . labelled

Delivered to site ready for fixing •
No loss of time in checking and sorting material • No loss of material due to prolonged storage on site •

A complete service of
DESIGN, FABRICATION AND FIXING
for all types of Reinforced Concrete
Construction.

T.C.JONES & Co.Ltd

REINFORCEMENT ENGINEERS

WOOD LANE, LONDON, W.12
BUTE STREET, CARDIFF
TREORCHY, GLAMORGAN



Telephone : Shepherds Bush 2020
Telephone : Cardiff 28786
Telephone : Pentre 2381



RAWLOOPS

You can have that shuttering erected or dismantled in *minutes*. For tapered walls or for reinforced walls (shuttering one side only) use Rawloops—you need no struts after the first lift! Two other big time-savers are Rawties (for shuttering both sides of a wall) and Rawhangers (for every size of R.S.J.)

These devices save time, timber and money. Write now for handsome technical brochure—'Lower the cost of raising the shuttering.'



ENDORSED BY FAMOUS BUILDING CONTRACTORS:

E. B. Badger & Sons Ltd. W. E. Chivers & Sons Ltd. Custodis (1922) Ltd. J. L. Eve Construction Co. Ltd. F. C. Construction Co. Ltd. Foundation (Plant) Ltd. W. & C. French Ltd. Gilbert-Ash Ltd. Holloway Bros. (London) Ltd. John Laing & Son Ltd. Wilson Lovatt & Sons Ltd. Sir Alfred McAlpine & Son Ltd. Sir Robert McAlpine & Sons Ltd. Marples, Ridgway & Partners Ltd. Mills Scaffold Co. Ltd. F. G. Minter Ltd. John Mowlem & Co. Ltd. Taylor Woodrow Construction Ltd. Trollope & Colls Ltd. Vibrated Concrete Construction Co. Ltd.



THE WORLD'S LARGEST MANUFACTURERS
OF FIXING DEVICES

THE RAWLPLUG CO. LIMITED · CROMWELL ROAD · LONDON S.W.7



Prestressed concrete sections made with Ciment Fondu and used in the construction of a tobacco factory at Bristol.

By courtesy of C. W. Glaser & Partners

PRESTRESSED CONCRETE STRUCTURAL UNITS

Cast one day—in service the next

The advantages of Ciment Fondu are significant in the manufacture of prestressed concrete. Rapid hardening and the high structural strength obtained in only 6-8 hours after placing effect speedier production and lower overall manufacturing costs. Curing is required during 24 hours only instead of the several days usually needed. Steam curing is not only unnecessary but undesirable. Fewer stress beds are required and the tension wires can be cut within 24 hours of casting. Ciment Fondu also possesses high resistance to chemical action, as proved by its applications in connection with sulphates, sea water, marsh land, waste flue gases, etc., etc., and its use therefore gives protection to the prestressing wires.



Concrete Rock-Hard within one day

LAFARGE ALUMINOUS CEMENT CO. LTD., 73 Brook St., London, W.1. Tel.: MAYfair 8546

AP 7-1959



THE
"LIGHTEST JACK
IN THE WORLD"

WITH
15 to 50
TONS CAPACITY



TANGYE



There are a thousand and one "Jobs for Hydralites". These, the lightest jacks available, are easily moved to difficult positions by one man without fear of personal injury; are self-contained and operated by a short handle with ease. Capacities of 15 and 25 tons with 6" or 12" lift, or 50 tons with 6" lift only, are available. **The 15 tons 6" power-lift model weighs only 24 lbs.** Claw attachments are available which enable jacking under loads with only 2 or 3 inches clearance, and screwed-ram models are provided when required to lock the load in a precise position.

The
HYDRAULICS DIVISION
of
TANGYES LIMITED
SMETHWICK · BIRMINGHAM



AD No. 18

**WATERTIGHT
LININGS
FOR
RESERVOIRS
SWIMMING
BATHS, ETC.**



**LININGS
FOR
TUNNELS,
SEWERS,
TANKS.**

*Specialists in the Repair and Reconditioning of
Reinforced Concrete Structures, etc.*

THE


GUNITE
CONSTRUCTION CO. LTD

WESTERN HOUSE, HITCHIN, HERTS.


STONE COVERING PAINT

WHAT IT IS - AND HOW TO APPLY IT

THIS BOOK WILL TELL YOU



STONE COVERING—Fine Stipple



STONE COVERING—Coarse Stipple

You will find this booklet very useful. It describes the complete range of Stic B Products, their application and use by the Architect and Builder. Included also is a comprehensive report by the Building Research Station on the conditions under which our products were tested, and the impressive results that were achieved. Please write to our London office, when a copy will be sent you by return.

STIC B PAINT SALES LTD.

47 WHITEHALL, LONDON, S.W.1

Telephone : WHitehall 9958/9

Reinforced Concrete

DESIGN AND CONSTRUCTION

Cast Stone**Floors**

IN SITU AND PRECAST

Granolithic Pavings**Staircases****STUART'S****GRANOLITHIC CO. LTD.**

FOUNDED 1840

LONDON

105 Baker Street, W.1.

Telephone : Welbeck 2525/6.

EDINBURGH

48 Duff Street.

Telephone : Edinburgh 61506.

BIRMINGHAM

Northcote Road, Stechford.

Telephone : Stechford 3631/2.

MANCHESTER

Ashton Road, Bredbury, Stockport.

Telephone : Woodley 2677/8.

**GUNITE**

Systematic
repairs to
structures
based on
systematic
diagnosis
of defects

**GUNITE AND
CEMENTATION****WHITLEY MORAN
AND COMPANY LIMITED***Specialists in the repair of Engineering Structures***5 OLD HALL STREET
LIVERPOOL***Tel. CENTral 7975*

The Perfect CURE



The Perfect UNDERLAY

Curing with SISALKRAFT is simple and sure. Condensation, which forms beneath the SISALKRAFT, keeps the slab moist, even in hot weather. But SISALKRAFT does more than merely cure and protect concrete from pitting and staining. It retains the heat generated during hydration of the cement and so gives VALUABLE PROTECTION AGAINST FROST.

With its high bursting strength SISALKRAFT (Subsoil grade) takes good care of the underside of concrete, allowing full subgrade friction and ensuring maximum strength.

Information sheet, samples and prices on request.



ESTABLISHED 1857

J.H. SANKEY & SON, LTD.

Sole Distributors for British Sisalkraft Ltd.

ALDWYCH HOUSE, ALDWYCH, LONDON, W.C.2. 'Phone: HOLborn 6949 (20 lines). 'Grams: Brickwork Estrand, London.

JOHN HEATHCOAT'S WEAVING SHEDS

TIVERTON, DEVON

Prestressed concrete decreases costs in factory construction



Heathcoats factory at Tiverton, Devon, has recently been extended using prestressed concrete valley beams and northlight roof trusses. The first section uses six beams of 56 ft. span. The second phase consists of 14 beams arranged in two 50 ft. spans. The third and last section uses 10 beams of 108 ft. span.

**The design aspects of this project and others are published in brochure form. Write for your copy now.*

Sponsor: JOHN HEATHCOAT & CO. LTD.,
TIVERTON,
DEVON.

Architect: ALBC FRENCH,
F.R.I.B.A.,
BRISTOL.

Design by: STRESSED CON-
CRETE DESIGN
LTD., LONDON,
S.W.4.

Contractors: WM. COWLIN
& SON, LTD.,
BRISTOL.



Ever since prestressed concrete construction was first used in this country, designers, architects and civil engineers have specified "Wire by Johnsons." The reason is quality, built up on early experimental work with those specialist designers who studied and worked on the Continental development of this new building technique.

Johnsons have a long record of "Firsts" including indented wire for greater bonding and coils of 8 ft. diameter, from which the wire pays out straight.

wire was essential—

Johnsons of course!

MONK

of

WARRINGTON and LONDON

*are organised and equipped
to carry out*

STRUCTURAL ENGINEERING

REINFORCED CONCRETE AND

BUILDING CONSTRUCTION

*This organisation has been
responsible for the construction of many
major projects at Home and Overseas*

A. MONK & COMPANY LIMITED

Head Office:


Padgate, Warrington. Telephone: Warrington 2381

London Office:

75 Victoria Street, S.W.1. Telephone: Abbey 2651

Stamford Office: Tel.: Stamford 2487 Hull Office: Tel.: Hull 16641

REINFORCED CONCRETE BARS



Reinforced Concrete Bars to BS 785
(Mild, Medium or High Tensile Steels)
Straight or Cut and Bent to Specification
Rounds $\frac{1}{2}$ " Dia. and up
Squares $\frac{3}{4}$ " and up
Deformed or indented bars $\frac{3}{8}$ " up to $1\frac{1}{2}$ "



COLVILLES

LTD

FITNESS FOR PURPOSE STEELS

COLVILLES LTD 195 WEST GEORGE ST. GLASGOW C.2

New **BEA** hangars at London Airport
constructed quickly and easily thanks to



RAPID METAL Formwork

These pictures of the New B E A Hangars at London Airport, probably the largest project undertaken in the country in the combined use of reinforced and prestressed precast and *in situ* concrete, show how easily and quickly the 150 ft. span main beams were constructed with Rapid Metal Formwork. No wonder so many contractors are standardizing on Rapid Metal Formwork for all concrete construction.



Contract: B E A Hangars, London Airport.

Consulting Engineers to B E A:

Scott & Wilson, M.M.I.C.E.

Consulting Architects to B E A:

Ramsey, Murray & White, F.F.R.I.B.A.

Contractors:

Holland & Hannen and Cubitts Ltd.

You can depend on

Patentees and Sole Manufacturers:

RAPID METAL DEVELOPMENTS LTD.

109 Walnut Road, Park View, Birmingham 22B. Tel.: Birmingham 6021. London Office: 47 Victoria Street, S.W.1. Tel.: Abbey 4077. Glasgow Office: 26 Hibernian Street, Glasgow, G.2. Tel.: City 8512. Liverpool Depot: Great Britain Farm, Kirkby, Liverpool. Tel.: Simons Wood 1481. South Wales Depot: Bridge Road, Neumarlydd, Swansea. Tel.: Gowerston 3277. U.K. Patent Nos. 652,870 and 667,916. Protected by Patents in all countries.

RAPID METAL Formwork

Colcrete

COLLOIDAL CONCRETE

**● IN THE LARGEST PRESTRESSED
BRIDGE IN ASIA**





Illustration shows the first three of the 22 spans, each 150 ft. long

THE SONE BRIDGE INDIA

3,300 Ft. Long, 24 Ft.
between Kerbs. Designed
and constructed for
the Irrigation Department,
Uttar-Pradesh
by

**GAMMON INDIA LTD.
BOMBAY**



REINFORCED CONCRETE CONSTRUCTION



BEHIND THE FACADE
of brick and glass in this
group of Laboratory and
Workshop Buildings lies
the enduring strength of
**REINFORCED CON-
CRETE STRUCTURES
AND FOUNDATIONS**

Built by



TELEPHONE SIMONSWOOD 2601 (3 lines)

HAMMOND ROAD, KIRKBY INDUSTRIAL ESTATE, LIVERPOOL



**PRESTRESSED CONCRETE
PIPE BRIDGE
CONSTRUCTED BY**

This pipe bridge across the River Trent at Gunthorpe, near Nottingham, has a span of 250 ft. and a width of 10 ft. The City Engineer of Nottingham, Mr. R. M. Finch, O.B.E., M.I.C.E., supervised the work for the Water Engineer, Mr. B. W. Davies, M.I.C.E. Designers: Pre-Stressed Concrete Co., Ltd.

CROWLEY RUSSELL
& COMPANY LIMITED

**CIVIL ENGINEERING CONTRACTORS AND SPECIALISTS
IN REINFORCED AND PRESTRESSED CONCRETE**

16 BLYTHSWOOD SQUARE, GLASGOW, C.2.

TELEPHONE: CITY 6271

Cromer Pier....

The reconstruction of this 500-ft. pier on behalf of the Cromer Urban District Council is now approaching completion. The contract has included the replacement of main steelwork, columns, concrete and timber decking, etc. Consulting Engineers are Messrs. Lewis & Duvivier, Victoria Street, London, S.W.1.

Surveyor to the Council:
J. A. Haigh, Esq.,
A.M.I.S.E.

Resident Engineer:
S. M. Johnson, Esq.,
O.B.E., M.I.C.E.

*reconstruction
undertaken by*



CONCRETE PILING LTD



10 WESTMINSTER PALACE GARDENS ARTILLERY ROW LONDON SW1 PHONE ABBEY 1626/7
LADAS DRIVE BELFAST PHONE BELFAST 58100 WORKS RIVER ROAD BARKING PHONE RIPPLEWAY 2624

Output increased by two-thirds!

This machine is specifically designed for the mass production of SOLID blocks in sizes $18" \times 9" \times 2"$, $2\frac{1}{2}"$, $3"$ and $4"$ in thickness and is capable of making 550 units per hour by means of "Duplex" fittings.

Fittings as extras are also available for manufacturing HOLLOW blocks one at a time, having two cavities to standard measurements $18" \times 9" \times 3"$, $4\frac{1}{2}"$, $4\frac{1}{2}"$, $6"$, $8\frac{1}{2}"$ and $9"$ in width.

It is fitted with a large hopper and mechanically operated conveying gear, combined with a feeding box. The gear mechanism is automatically lubricated by an oil bath within the gear box.



TRIANCO K2, Mark 2.
Automatic Block-Making Machine.

Full specification will be sent on application.

TRIANCO LIMITED

IMBER COURT, EAST MOLESEY, SURREY

Telephone: EMBerbrook 3300.

Telegrams: Trianco, East Molesey.

TRIANCO

BLOCK-MAKING MACHINES

STEEL REINFORCING RODS IN STOCK

designed
cut to length
formed and bundled

JOYNSON HOLLAND (ENGINEERS) LTD


HIGH WYCOMBE

Telephone: High Wycombe 2700

BACK NUMBERS OF "CONCRETE and CONSTRUCTIONAL ENGINEERING"

The Publishers frequently have enquiries for back numbers of "Concrete and Constructional Engineering," generally from universities and similar institutions abroad. Readers who have copies published before 1954 (either bound or unbound) which they no longer require are invited to send a list of the dates to the Publisher, Concrete Publications, Ltd., 14 Dartmouth Street, London, S.W.1. Generally at least the published price can be offered for such back numbers.

★ ENTIRELY NEW HYDRAULIC BAR CROPPER



THIS ALL-BRITISH

ALLAM

BAR CROPPER

is specially designed
for Precast Concrete
Makers and Rein-
forced Concrete
Contractors

MAXIMUM CAPACITY: Up to
1-in. diameter bars, or multiples
of smaller diameter bars, includ-
ing rounds, squares and flats.

Other types also available with capac-
ities up to 1½" diameter bars.

E · P · ALLAM & CO. LTD.


LONDON: 45 Great Peter Street, S.W.1.

Telephone: Abbey 6353 (5 lines)

SCOTLAND: 39 Canwood St., Glasgow, C.8. Tel.: South 0186.

Works: Southend-on-Sea. Tel.: Eastwood 55243

NOW a **TANGYE** climbing jack for moving-form concrete construction



An Invitation

Civil Engineers who are interested in concrete buildings constructed by the "moving form" method of shuttering are invited to apply to Tangye Limited, and make an appointment to witness a demonstration of a recently developed Hydraulic application.

The modern building method, using climbing form-work, demands Hydraulic jacks, all deriving their power from one source—a small Hydraulic Pump unit. The whole lifting operation is then carried out by one man instead of a jacking crew as required by the old screw jack method. The adoption of the Hydraulic system greatly increases productivity and the speed of building construction.

Ask for further information

TANGYE LIMITED CORNWALL WORKS SMETHEWICK BIRMINGHAM
AREA OFFICES
LONDON W 1 60 CROSVENOR STREET MANCHESTER 2 5 CROSS STREET
GLASGOW C 2 13 WATERLOO STREET


TANGYE

HYDRAULIC DIVISION

BUILT ON A CENTURY OF HYDRAULIC EXPERIENCE

THE PORTASILO SYSTEM REG'D

**The world's most
highly developed
fully portable
bulk cement
equipment**



The Type 201 (20 tons nominal capacity) PORTASILO.

*The automatic
weighing device
is instantly ad-
justed against the
calibrated scale.*

The PORTASILO system exploits to the full the advantages of using bulk cement and utilises the pneumatic delivery system now offered by the leading cement manufacturers. Its use can effect savings of 18/- per ton of cement used. This proved and established system can be seen operating in most parts of the country. The PORTASILO is fully portable and the Type 105 Model of 10 tons nominal capacity is light enough to be man-handled. Automatic weighing of the cement is provided by the FULLWEY Mechanical Cement Man. The PORTASILO illustrated is the Type 201 of 20 tons nominal capacity. Other models of 10 tons capacity and upwards are available.

Write to-day for full details.

Erected in minutes, the PORTASILO has unique advantages

- ★ No prepared foundations.
- ★ No power required for its operation.
- ★ No erection or dismantling problems.
- ★ No assembly joints to create trouble.

The system eliminates:

- ★ Unloading of cement by hand.
- ★ The need for a cement man behind the concrete mixer.
- ★ Waste.
- ★ The disposal of empty cement bags.

PORTASILO

LIMITED

*Covered by patent
applications in
Great Britain and
the principal coun-
tries of the world.*

BLUE BRIDGE LANE, YORK. Telephone: YORK 4872 (8 lines)

CONCRETE AND CONSTRUCTIONAL ENGINEERING

INCLUDING PRESTRESSED CONCRETE

Volume L, No. 8.

LONDON, AUGUST, 1955.

EDITORIAL NOTES

Liberal Education in a Technical Age.

NOTES in this journal during the past twenty years or so deploring the lack of education of many of the younger technologists have resulted in the receipt of many resentful letters. That the views we have expressed are not unfounded, however, is shown by the fact that the problem has in recent years increasingly been debated in Parliament and elsewhere, and much concern has been expressed at the tendency for men entering the professions to be technologists in one narrow branch of knowledge rather than what Bacon described as "whole men". The latest inquiry into the problem is that conducted by a committee appointed by the National Institute of Adult Education, whose report * is now published. This report, like others before it, confirms all that we have written. It agrees that the possession of a General Certificate of Education in approved subjects by a child of sixteen years of age "does not amount to much", although it is commonly the only standard of education required for the acceptance of a student of a technical subject. It agrees that cramming in a technical subject from that age onwards leaves no room for further general education, although one or two technical colleges make some attempt to influence their students to improve their general education. The standard of English of such students is agreed to be often deplorable, even in the case of men who have obtained a university degree, and attention is directed to the need to develop in men trained in science and technology the qualities that will fit them to deal with problems of policy, management, and human relations—or, it may be added, to make them good scientists and technologists.

The report emphasises the duty of teachers of technical subjects to pay attention to the students' use of English as an essential means of thought and communication. Many of the teachers who replied to a questionnaire agreed with this view, but others thought that their only duty was to teach a vocation in which the student could earn a living. It is deplorable that teachers should be content to accept such a narrow view of their responsibilities, but it may be that they themselves are not all capable of doing more. The need for precise language is as necessary in science and technology as it is in the law, yet how often do we find teachers who confuse their students by the misuse of simple words? It is, for example, fairly common to see and hear a load on a structure or a foundation

* "Liberal Education in a Technical Age." [London: Max Parrish & Co., Ltd. Price 6s.]

called a reaction, whereas in fact it is the opposite—it is the action or force that causes a reaction. A lecturer some time ago excused his misuse of this word on the ground that when he was a student it was so used by his lecturer, and neither of them knew that reaction was the opposite of action. In the Code of Practice for Foundations issued by the Institution of Civil Engineers last year the resistance of the earth under a foundation is called "earth pressure", which is the opposite of the truth. Prestressing has also resulted in terms which are frequently used in the opposite sense of their true meaning. For example, prestressed members are often described as pre-tensioned, which can only mean that they are stretched before they are erected, whereas in fact the exact opposite is the case—they are compressed. A common excuse for this misuse of words is that "we all know what we mean by them", but how stupid it is to confuse the mind by using ordinary words in the opposite sense of their true meaning in a technical school and in published matter on structural engineering. It should be remembered that large numbers of British technical publications are exported to countries where the readers know only the meanings given to words in a dictionary, and who are not told that the writer does not always say what he means—for example, that when he writes pressure he may mean resistance, that tensioned may mean compressed, that reaction may mean an applied force, and so on.

Last year a symposium was held in London on "Mix Design and Quality Control of Concrete". Here the ungrammatical slang of the navy is used in the title of the symposium and throughout many of the papers. In a philosophical discussion there is no excuse for using the verb "mix" variously as a noun and as an adjective. Indeed, we should be very stupid to mix design if we wished to design a mixture. Also, the misuse of the word quality as an adjective destroys the sense of the title; what is meant is control of the quality of concrete rather than the quality of the control. The fact that the Department of Scientific and Industrial Research uses this bad English is not a good reason why others should do so; official bodies should rather set an example.

The report places some of the responsibility on professional institutions that are content to be concerned only with technical knowledge in their examinations for membership, with the result that technical education is concentrated on the task of working for examinations. This problem was put by the committee to some of the professional institutions, but generally the reply was that they were concerned only with competence in "specialised techniques". The committee's main recommendation is that the technical schools should pay more attention to giving a liberal education as well as technical training to future scientific and technological workers. It is suggested in this report that the time necessary for broader education be found by omitting some of the details now required at examinations but which need not be remembered afterwards, and to this end it is further suggested that students be allowed to use reference books at examinations to save them "memorising material which no sensible practitioner tries to carry in his head". This is contrary to the present conception of the purpose of an examination, but it is an idea that may compare well with a system in which memory may be more important than ability, and by which men who cannot spell simple words or put their thoughts intelligibly on paper can obtain a university degree which should be a hallmark of education as well as of technical competence.

Design of Non-Prismatic Members.

A Numerical Method.

By H. P. VASWANI, B.Eng., D.I.C.

THE moment-distribution method requires the determination of carry-over factors and distribution factors at every joint. These can be easily calculated when the members have constant moments of inertia; the carry-over factor for such a member is 0.5 and its stiffness is proportional to its moment of inertia divided by its length. If the moment of inertia is not constant, strain-energy methods are often used. However, when the moment of inertia does not follow a simple mathematical curve, integration of the expressions obtained by strain-energy equations may be too involved to permit an easy solution, or sometimes may even be insoluble. In such cases numerical methods may be used. The application of relaxation methods was recently published.⁽¹⁾ In this article Simpson's rule is used to find the stiffnesses and carry-over factors of non-prismatic members.




Fig. 1.

According to Simpson's rule the area A'' of the two adjacent strips shown shaded in Fig. 1 can be written as $A'' = \frac{h}{3}(a_1 + 4a_2 + a_3)$, where a_1, a_2 , etc., are ordinates and h is the distance between the ordinates. Hence the area A of the diagram, divided into an even number of strips, is obtained by adding areas of successive strips and can be written

$$A = \frac{h}{3}(a_1 + 4a_2 + 2a_3 + 4a_4 + \dots + 2a_{n-2} + 4a_{n-1} + a_n).$$

Since the rule assumes that the ordinates a_1, a_2, a_3 , etc., are joined by a second-degree parabola, for accurate results, only four intervals are necessary if the curve is parabolic, and only two if the curve is linear. For a smooth curve of general form Simpson's rule can be extended to give greater accuracy by including differences of a higher order in the Stirling formula, which result in the expression

$A'' = \frac{h}{90}(-a_2 + 34a_3 + 114a_4 + 34a_5 - a_6)$ for the area of the two adjacent strips shown shaded in Fig. 1.

Simpson's rule can also be used to integrate one diagram with another⁽²⁾, and hence can be applied to problems in structural analysis; here its use is extended to integrate three diagrams with one another.

Fig. 2 shows a beam AB of varying moment of inertia. The carry-over factor to B and the slope of the tangent at A are to be determined when a moment is

applied at A. A bending moment M_A is applied at A and it is assumed that A is pinned and B encastré. The ratio of the bending moment carried over (to B) to M_A is the carry-over factor. The span AB is divided into a convenient even number of short lengths n . The bending-moment diagram is drawn, and values $m_1, m_2, m_3 \dots m_n$ are indicated in terms of M_A and M_B , where M_B is unknown. Similarly, diagrams for $\frac{I}{EI}$ and x are drawn and values $i_1, i_2, i_3 \dots i_n$ in terms of I_0 and $x_1, x_2, x_3 \dots x_n$ are shown in terms of l_0 .

By area-moment theorem No. I, $\int \frac{M}{EI} dx = \theta_A$, that is the bending-moment diagram is to be integrated with the diagram for $\frac{I}{EI}$ and equated to θ_A ; this may be rewritten

$$\frac{h}{3}(m_1 i_1 + 4m_2 i_2 + 2m_3 i_3 \dots 4m_{n-1} i_{n-1} + m_n i_n) = \theta_A.$$

By area-moment theorem No. II, $\int \frac{Mx}{EI} dx = \delta_A = 0$, where x is measured from A. This equation may be rewritten

$$\frac{h}{3}(m_1 i_1 x_1 + 4m_2 i_2 x_2 + 2m_3 i_3 x_3 \dots 4m_{n-1} i_{n-1} x_{n-1} + m_n i_n x_n) = 0.$$

From these two equations the relationship between M_A, M_B , and θ_A is derived




Fig. 2.




Fig. 3.

and is used in the following example to determine distribution factors for use in moment-distribution analyses.

EXAMPLE 1.—The end supports of a two-span continuous beam (Fig. 3) are encastred and the spans are of equal length. In the first span the moment of inertia has a constant value I_0 ; in the second span it varies from I_0 at the central support to $2I_0$ at the encastred end. The stiffness at the end is defined as the moment required to rotate that end, when it is assumed to be simply supported, through a unit angle when the other end is fixed.

In the span AB the applied bending moment M_B is such that the tangent at B rotates through an angle θ_B when B is assumed to be simply supported. Then the area of $\frac{M}{EI}$ diagram, $\int \frac{M}{EI} dx = \theta_B = 1$, is

$$\frac{M_A + M_B}{2} \cdot \frac{l}{EI_0} = 1 \quad (1)$$

The deflection δ_B measured from the tangent at A = $\int \frac{Mx}{EI} dx = 0$, where x is measured from B, is

$$\frac{l}{2} \cdot \frac{1}{3E} \left\{ \frac{M_A l}{I_0} + 4 \cdot \frac{M_A + M_B}{2} \cdot \frac{l}{2} \cdot \frac{1}{I_0} \right\} = 0 \quad (2)$$

From (1) and (2), $M_B = \frac{4EI_0}{l}$ is the stiffness of BA at B.

Similarly for beam BC,

$$\frac{l}{2} \cdot \frac{1}{3E} \left\{ \frac{M_C}{2I_0} + 4 \cdot \frac{M_C + M_B}{2} \cdot \frac{3}{4I_0} + \frac{M_B}{I_0} \right\} = 1 \quad (3)$$

$$\frac{l}{2} \cdot \frac{1}{3E} \left\{ \frac{M_C l}{2I_0} + 4 \cdot \frac{M_C + M_B}{2} \cdot \frac{3}{4I_0} \cdot \frac{l}{2} \right\} = 0 \quad (4)$$

From (3) and (4), $M_B = \frac{60}{13} \cdot \frac{EI_0}{l}$ is the stiffness of BC at B.

Hence the distribution factors are, for BA, $\left[\frac{4EI_0}{l} \right] \div \left[\frac{4EI_0}{l} + \frac{60}{13} \cdot \frac{EI_0}{l} \right] = 0.465$

and, for BC, $1 - 0.465 = 0.535$.

EXAMPLE 2.—Find the fixed-end moments in the encastred beam (Fig. 4) whose moment of inertia varies from I_0 at A to $2I_0$ at B. The beam has a uniformly-distributed load of intensity w .

From area-moment theorem No. 1, $\int \frac{M}{EI} dx = 0$, that is the area of the

$\frac{M_0}{EI}$ diagram is equal to the area of the $\frac{M_F}{EI}$ diagram. Integrating the M_0 diagram

with the $\frac{1}{EI}$ diagram,

$$\frac{l}{4} \cdot \frac{1}{3E} \left\{ 4 \cdot \frac{7}{8I_0} \cdot \frac{3M_0}{4} + 2 \cdot \frac{3}{4I_0} \cdot M_0 + 4 \cdot \frac{5}{8I_0} \cdot \frac{3M_0}{4} \right\} = \frac{1}{2} \frac{M_F l}{EI_0} = \frac{wl^3}{16EI_0}$$




Fig. 4.

Integrating the M_F diagram with the $\frac{1}{EI}$ diagram,

$$\frac{l}{2} \cdot \frac{1}{3E} \left\{ \frac{M_A}{I_o} + 4 \cdot \frac{M_A + M_B}{2} \cdot \frac{3}{4I_o} + \frac{M_B}{2I_o} \right\} = \frac{5}{12} \cdot \frac{M_A}{EI_o} \cdot l + \frac{1}{3} \cdot \frac{M_B}{EI_o} \cdot l.$$

Therefore

$$\frac{5}{12} \cdot \frac{M_A l}{EI_o} + \frac{1}{3} \cdot \frac{M_B l}{EI_o} = \frac{wl^3}{16EI_o} \quad (5)$$

From area-moment theorem No. II, $\int \frac{Mx}{EI} dx = 0$. Integrating the M_o diagram with the $\frac{1}{EI}$ and x diagrams, where x is measured from B,

$$\frac{l}{4} \cdot \frac{1}{3E} \left\{ 4 \cdot \frac{7}{8I_o} \cdot \frac{3M_o}{4} \cdot \frac{3l}{4} + 2 \cdot \frac{3}{4I_o} \cdot M_o \cdot \frac{l}{2} + 4 \cdot \frac{5}{8I_o} \cdot \frac{3M_o}{4} \cdot \frac{l}{4} \right\} = \frac{17}{64} \cdot \frac{M_o l^2}{EI_o} = \frac{17}{512} \cdot \frac{wl^4}{EI_o}.$$

Integrating the M_F diagram with the $\frac{1}{EI}$ and x diagrams, where x is measured from B,

$$\frac{l}{2} \cdot \frac{1}{3E} \left\{ \frac{M_A}{I_o} \cdot l + 4 \cdot \frac{M_A + M_B}{2} \cdot \frac{3}{4I_o} \cdot \frac{l}{2} \right\} = \frac{7}{24} \cdot \frac{M_A l^2}{EI_o} + \frac{3}{24} \cdot \frac{M_B l^2}{EI_o}.$$

Therefore

$$\frac{7}{24} \cdot \frac{M_A l^2}{EI_o} + \frac{3}{24} \cdot \frac{M_B l^2}{EI_o} = \frac{17}{512} \cdot \frac{wl^4}{EI_o} \quad (6)$$

$$\text{From (5) and (6), } M_A = \frac{15}{208} . w l^2 \text{ and } M_B = \frac{20.25}{208} . w l^2.$$

[REFERENCES: (1) E. Markland, "The Calculation of Elastic Properties of Non-Prismatic Structural Members," *Civ. Eng. & P.W. Review*, Vol. 49, No. 571, January 1954. (2) A. L. L. Baker, "Further Research in Reinforced Concrete, and its Application to Ultimate Load Design," *Proc. I.C.E.*, Aug. 1953 (No. 2), Vol. 2, Part III.]

The late Professor Gustave Magnel.

It is with profound regret that we record the death of Professor Gustave Magnel, which occurred suddenly in Ghent on July 5, at the age of 60, as the result of a heart attack. By his passing the world loses one of its greatest civil engineers, whose specialisation in reinforced concrete and prestressed concrete had a great influence in the development of these new materials during the past thirty years.

After graduating at Ghent University, he came to England in 1914 and was one of the band of Continental engineers who were employed by the late D. G. Somerville for the primary purpose of training British graduates at a time when little attention was given to reinforced concrete at British universities and when textbooks were few. Somerville's far-sighted effort in using his office as a well-paid post-graduate course was of inestimable value to the men trained in his office and who remember with gratitude both him and Magnel, who soon became Somerville's chief engineer. At one time, indeed, Somerville had the temerity to open an office in Paris for the design and erection of reinforced concrete structures, and Magnel took charge of this office.

In 1919 Magnel returned to the University at Ghent, where he soon became Professor of Reinforced Concrete. He had a gift for lucid exposition, and was a great teacher. His books "*Cours de Stabilité des Constructions*," "*Pratique du Calcul du Béton Armé*," and "*Le Calcul Pratique des Poutres Vierendeel*" are masterly works that are treasured by many engineers outside Belgium. One of his activities was to develop the laboratory at Ghent until it was one of the best in the world. He had little use for tests on small-scale models, and whenever possible insisted on testing full-



size members, either in the laboratory or on the site.

During the last war, when Belgium was occupied and he had no access to outside information, he studied the possibilities of prestressed concrete and produced his well-known "Belgian" system. Magnel soon became an enthusiastic advocate of the new method of construction, and since the war his system has been largely used in many countries of the world. Like his other published works, his book "*Prestressed Concrete*" is notable for its clear exposition and avoidance of all that had not in his opinion been proved to be sound. It is typical of his outlook on engineering that in this book, while other systems are adequately described, all the examples of prestressed concrete

work are structures that he designed himself or whose design and construction he had supervised. He preferred to write only of what he knew and to take nothing at second hand, and as he had designed and built most types of structures in prestressed concrete the book did not suffer.

His last effort was to design a prestressed concrete tower more than 2000 ft. high (about twice the height of the Eiffel tower) for the Brussels World Fair of 1958, and when he showed us the drawings a few months ago he said that he would retire when this was built. His tower was to be a circular shaft about 200 ft. diameter at the bottom and tapering towards the top, and would be built of precast members cast on the site. There was to be a central lift-shaft and rooms for letting on the 200 or so floors. The top ten stories were to be used for the broadcasting of television programmes and the rest would be let for other

purposes. The Belgian Government is now considering the project, which would cost about £3,000,000.

Magnel was very proud to have been elected a Member of the Belgian Royal Academy, and was intensely patriotic; during the war he was imprisoned by the Germans for his refusal to collaborate with them. His greatest pleasure was to train good Belgian engineers who would work in other countries and add to the prestige of his country, and it is notable that he gave the name of his country, rather than his own, to his system of prestressed concrete. He did much engineering work for the Belgian Government. In 1945 he was elected one of the first members of the United Nations Educational, Scientific and Cultural Organisation. He will be mourned by a host of friends throughout the world, who will sadly miss his genial presence and his never-failing helpfulness.

Book Reviews.

"Data Book for Civil Engineers." Vol. 3, "Field Practice." By Elwyn E. Seelye. (London: Chapman and Hall, Ltd. Second edition, 1954. Price 60s.)

This is one of a series of three American books of data for civil engineers. Part I (277 pages) deals with the problems and duties of inspectors of works. Part II (105 pages) gives comprehensive notes, tables, and formulae on surveying. Transition curves and spirals are fully dealt with, and the tables for the measurement of earthworks are particularly useful.

Part II is divided into sections, and the largest (58 pages) describes the examination, classification, and testing of subsoils. The bearing resistance of soils is discussed, but there is little information about earth pressure, embankments, and cuttings. Most of the work described would normally be carried out to a specification written by an engineer experienced in this class of work, so that much of the data appears to be unnecessary; some of this space could have been usefully given to notes on temporary site works in timber.

Other sections deal with equipment and construction methods, concrete, masonry, structural steel, timber, bridges, piles,

bituminous paving, and sewage and drainage works. Each section includes a list of items for the inspector to check and also gives examples of report sheets. In the section on concrete are notes on the testing of aggregates, reinforcement, concreting in cold weather, and air-entrained concrete. The data on concrete mixtures are ample, and the tables relating the weight of concrete to its probable strength are useful. The "Engineering News" pile-driving formulae are given, but tables of allowable loads are based on modified formulae.

"Solution of Problems in Surveying and Field Astronomy." By H. W. Stephenson. (London: 1955. Sir Isaac Pitman & Sons, Ltd. Price 25s.)

This is a collection of problems in surveying, geodesy, and field astronomy based generally upon questions set in the examinations of the University of London and the Institution of Civil Engineers. In addition to the problems for which there are completely worked solutions, there are many to which the answers only are given. The book should be useful to students and to engineers in practice.

A New Method of Prestressing Circular Reservoirs.

AN unusual method of constructing circular reservoirs with a capacity greater than about 500,000 gallons was described by MM. Marcel and André Reimbert in the French journal "Travaux" for October, 1953, from which the following is abstracted.

The wall (Fig. 1) comprises two leaves of which the inner is a series of horizontal arches of small radius and the outer is polygonal, the springings of the arches and the ends of the outer facets being monolithic (Fig. 2). The radius of the centre-line of an arch is about 3 ft. and the "rise" is one-third of the radius. The length of each facet of the external leaf is about 5 ft. 2 in. Steel shutters (Fig. 3) were used.

The wall has a sliding joint at the base so that direct stresses only are caused by the pressure of the contained liquid. The reinforcement in the arches and the secondary reinforcement is mild steel; the horizontal reinforcement which acts as a tie in the outer part of the wall is of high-tensile steel.




Fig. 1.—Plan and Section.



Fig. 2.—Horizontal Section through Wall.



Fig. 3.—Reinforcement and Shutters for Part of Wall.

Construction.

The reservoir is constructed in four stages (Fig. 4). First the floor is laid on weak concrete placed over the site. Secondly a layer of bituminous material is placed around the periphery to form a sliding joint for the wall, and on top of this the concrete base of the wall is cast with reinforcement projecting to lap with the reinforcement in the first lift of the wall. The reinforcement is made up in cages (Fig. 5). Thirdly the wall is cast to the full height (Fig. 6). This may be done in either of two ways: (1) After the reinforcement is placed the arches only may be cast as shown in Fig. 7a with the ties left exposed between the springings, or (2) the arches and the external polygonal leaf are cast (Fig. 7b) leaving a gap of about 6 in. in the centre of each facet; in this case the tie-bars passing through the outer part of the wall are painted with bitumen before the concrete is cast. The bituminous joint between the toe of the wall and the floor is also made at this time. When the concrete in the wall and

floor is sufficiently strong the reservoir is filled and the increase in diameter due to the internal pressure elongates the tie-bars. The remainder of the external part of the wall is then concreted and is carefully cured to reduce shrinkage and creep. When this concrete is sufficiently strong the reservoir is emptied and the tie-bars compress the concrete in the outer part of the wall due to their elastic recovery as the hydraulic pressure is reduced. Thus when the tank is refilled the arches are in compression and there is no tensile stress in the concrete in the outer part of the wall.

The compressive stress in the arches is small. Consider for example a single arch (Fig. 8). If w is the density of the liquid, H the height of liquid above the point considered, t the thickness of the arch, and r the radius of curvature of the centre-line of the arch, the compressive




Fig. 4.—Section through Wall and Base showing Order of Casting.




Fig. 5.—Reinforcement at Base of Wall.




Fig. 6.—Casting the Walls.

force in the arch is wHr and the stress f is $\frac{wHr}{t}$, so that with a reservoir 30 ft. high in which the arches are $2\frac{1}{2}$ in. thick and have a radius of 3 ft.

$$f = \frac{62.5 \times 30 \times 3}{2.5} = 225 \text{ lb. per square inch.}$$

Comparison of Quantities of Materials.

The following example is given to show the quantities of materials required for a reservoir designed by this method compared with the quantities required for a reservoir of the same capacity designed




Fig. 7.




Fig. 8.

in the usual manner. The reservoir has a capacity of 1,770,000 gal. and is 26 ft. 3 in. high. The quantities for the common type of reservoir are given first. Concrete in wall and floor, 612 cu. yd. (342 cu. yd.); reinforcement, 59 tons (7.9 tons of mild steel and 14.125 tons of

high-tensile steel); internal waterproof lining, 2300 sq. yd. (2540 sq. yd.). It is stated that the cost of a reservoir built in the manner described is less than one of the usual type, and that by the use of precast arches a further saving can be made.

Compacting Soil by Vibration.

THE machine shown in Fig. 1 is one of a series developed by Vibro-Plus Products, Inc., of Woodside, N.Y., U.S.A., for compacting soils. The machine illus-



Fig. 1.

trated weighs 3 tons, and is driven by a 25-h.p. diesel engine. The front cylinder is 4 ft. 10 in. long by 4 ft. diameter, and is vibrated at variable frequencies between 1400 and 1600 vibrations per minute; at maximum frequency the

centrifugal force of the vibration is about 7 tons. Tests have shown that three passes of the roller over silty sand produced a compaction of 95 per cent. to a depth of 1 ft. and that six passes produced 100 per cent. compaction at that depth. Two passes at a speed of two miles per hour produced 95 per cent. density to a depth of 2 ft. in the case of soil comprising 80 per cent. of fine sand, 12 per cent. of coarse sand, and 8 per cent. of silt and clay.

Heavy Loads on Piles.

A BRIDGE in California, U.S.A., is to be carried on 238 piles each designed to carry a load of 225 tons. The piles are H-shape in cross section. A 14-in. pile of this shape, 138 ft. long, was driven to a solid bearing, and loaded with 45 tons. The total settlement under this load was $\frac{3}{4}$ in., and the settlement on removal of the load was $\frac{1}{4}$ in. This is thought to be the greatest load ever imposed on a pile of this shape. The contractors are the Duncanson-Harrelson Co. and the Pacific Bridge Co. The method of loading the pile is described in "Engineering News-Record" for February 24, 1955.

"Lift-up" Floor Construction.

THE "lift-up" method of floor construction is being used for floors with a total area of 215,000 sq. ft. in three-story barracks in Virginia for the United States Navy. The same system is being used at other large barracks now in course of construction in the U.S.A. The saving in cost compared with in-situ floors is estimated to be nearly 10 per cent.

At the Virginia barracks (Fig. 1) the ground-floor slab was laid first, and on this were cast the two upper floors and the roof. The wall columns are each

the second floor and roof were then concreted in the same manner, each separated from the next by paraffin emulsion. Each slab measured 53 ft. by 76 ft., and was lifted by the collars on twelve columns.

An hydraulic jack was placed on the top of each column, and from each jack a threaded rod extended on either side of the column to the lifting collars, to which they were fixed by lugs. The jacks were operated and the slabs were raised at the rate of about 5 ft. per hour.




Fig. 1.—Floors Cast at Ground Level and Hoisted into Position.

formed of two 8-in. by 8-in. by $\frac{1}{2}$ -in. steel angles and are spaced at 22-ft. centres transversely and at 20-ft. centres longitudinally. When the columns were erected the side-forms were fixed for the ground floor, the reinforcement and all pipes and services were laid in position, and the slab was concreted. Eighteen hours later the top of this slab was coated with a preparation with a base of paraffin. Lifting collars were fixed to the steel columns, and the slab for the first floor was concreted. The slabs for

When each slab arrived at the required height, steel blocks were welded to the columns below the collars to support the slab. When the roof slab was fixed, the lugs were removed from the threaded rods and lowered for use in lifting the next slab. The first and second floors are 9 in. thick and the roof $7\frac{1}{2}$ in. thick. They are reinforced in the normal manner. The height of each floor in these structures is about 11 ft.

The slabs were raised by N.Y. Lift Slabs, Inc., of San Antonio, Texas.




Fig. 2.

Then the maximum stress in the concrete c is

$$\frac{4W(1 + \sin \phi)}{D^2 \times y}$$

and the maximum stress in the steel t is

$$\frac{cm(d \cos \theta - \sin \phi)}{1 + \sin \phi}$$

where θ is the angle between the plane of the bending moment and the diameter of the column drawn through the bar farthest from the neutral axis in the tensile side of the column.

Since only that part of the line which cuts the curve is necessary, it need be drawn only between the two values of ϕ concerned. There will be only tensile stresses if e exceeds about 0.125, and as this value increases the value ϕ will

decrease from a maximum of $\frac{\pi}{2}$ to a negative quantity when e is infinity, that is when W is zero.

EXAMPLE.—A column of 12 in. diameter reinforced with six $\frac{3}{4}$ -in. bars having $1\frac{1}{2}$ -in. cover is subjected to an axial load of 30,000 lb. and a bending moment of 90,000 in.-lb.

$$d = \frac{8.25}{12} = 0.6875;$$

$$e = \frac{90,000}{30,000 \times 12} = 0.25;$$

$$r = \frac{2.65 \times 4}{3.14 \times 12^2} = 0.0234;$$

$$L = \frac{3.14 \times 15 \times 0.0234 \times 0.6875^2}{4 \times 0.25} = 0.52.$$

Value of ϕ	Values of y
-0.5	$\frac{0.0843}{0.25} + 0.52 = 0.737$
0	$\frac{0.1964}{0.25} + 0.52 = 1.305$
0.5	$\frac{0.3385}{0.25} + 0.52 = 1.873$
0.7	$\frac{0.3695}{0.25} + 0.52 = 1.998$
1.1	$\frac{0.3914}{0.25} + 0.52 = 2.087$
1.5	$\frac{0.3927}{0.25} + 0.52 = 2.090$

By plotting on the graph the values of y for $\phi = 0$ and $\phi = 0.5$ only and joining

August, 1955.

them with a straight line it is found that a curve representing r equals 0.0234, interpolated between those for r equals 0.02 and 0.03, is cut by the line when ϕ is 0.347 and y is 1.7. Therefore

$$c = \frac{4 \times 30,000(1 + \sin 0.347)}{144 \times 1.7} = 658 \text{ lb.}$$

per sq. in.

If θ equals $\frac{\pi}{6}$ (30 deg.), then

$$t = \frac{658 \times 15 \left(0.6875 \cos \frac{\pi}{6} - \sin 0.347 \right)}{1 + \sin 0.347} = 1875 \text{ lb. per sq. in.}$$

Appendix.

If AB is the neutral axis in a circular section resulting from the application of an axial load W and a bending moment M , then the total compressive force in the concrete is equal to the volume of the ungula ABCD (Fig. 1) of a circular prism where CD represents the maximum compressive stress in the concrete.

If the boundary ACB of the area being compressed subtends an angle 2α at the centre, then the area of ACB is

$$\frac{D^2}{4} (\alpha - \sin \alpha \cos \alpha)$$

and the depth of the neutral axis EC is $\frac{D}{2} (1 - \cos \alpha)$. The depth E'C' of any plane A'C'B' distant x from D and subtending an angle 2β at the centre is

$$\frac{D}{2} (1 - \cos \beta), \text{ or } \frac{x D}{2c} (1 - \cos \alpha).$$

Therefore $\cos \beta = 1 - kx$, where

$$k = \frac{1 - \cos \alpha}{c}, \text{ and, by differentiating, } -\sin \beta d\beta = -k dx.$$

$$\text{Area A'C'B'} = \frac{D^2}{4} (\beta - \sin \beta \cos \beta).$$

Therefore volume ABCD

$$\begin{aligned} &= \int_0^c \frac{D^2}{4} (\beta - \sin \beta \cos \beta) dx \\ &= \frac{D^2}{4k} \int_0^\alpha (\beta - \sin \beta \cos \beta) \sin \beta d\beta \\ &= \frac{D^2}{4k} \left[\sin \alpha - \alpha \cos \alpha - \frac{\sin^3 \alpha}{3} \right] \end{aligned}$$

$$= \frac{D^2 c \left(\sin \alpha - \alpha \cos \alpha - \frac{\sin^3 \alpha}{3} \right)}{4(1 - \cos \alpha)}$$

Since, in most cases, α exceeds $\frac{\pi}{2}$ it is convenient to substitute $\frac{\pi}{2} + \phi$ for α . Therefore volume ABCD

$$\begin{aligned} &= \frac{D^2 c}{4(1 - \cos \alpha)} \left(\frac{3}{4} \sin \alpha - \alpha \cos \alpha + \frac{\sin 3\alpha}{12} \right) \\ &= \frac{D^2 c}{4(1 + \sin \phi)} \left[\frac{3}{4} \cos \phi + \left(\frac{\pi}{2} + \phi \right) \sin \phi - \frac{\cos 3\phi}{12} \right] \\ &= \frac{D^2 c Y}{4(1 + \sin \phi)} \quad \quad \quad (1) \end{aligned}$$

where Y is the expression between the square brackets.

The moment of the area ACB about the centre

$$= \frac{D^3}{4} \int_0^{\alpha} \cos \alpha \sin^2 \alpha \, d\alpha = \frac{D^3}{12} \sin^3 \alpha.$$

Therefore the moment of any plane A'C'B' about the centre $= \frac{D^3}{12} \sin^3 \beta$, and the moment of the volume ABCD about the centre

$$\begin{aligned} &= \frac{D^3}{12} \int_0^{\pi} \sin^2 \beta \, d\beta = \frac{D^3}{12k} \int_0^{\pi} \sin^4 \beta \, d\beta \\ &= \frac{D^2 c}{96(1 - \cos \alpha)} \left(3\pi - 2 \sin 2\alpha + \frac{\sin 4\alpha}{4} \right) \\ &= \frac{D^2 c}{96(1 + \sin \phi)} \left[\frac{3\pi}{2} + 3\phi + 2 \sin 2\phi + \frac{\sin 4\phi}{4} \right] \\ &= \frac{D^2 c X}{96(1 + \sin \phi)} \quad \quad \quad (2) \end{aligned}$$

where X is the expression between the square brackets.

From the geometry of the section and the stress-variation diagram, the stresses in each bar are related to the maximum compressive stress as follows:

$$\begin{aligned} \frac{D}{2(1 - \cos \alpha)} &= \frac{mD}{2} \frac{t_1}{(d \cos \theta - \cos \alpha)} \\ &= \frac{t_2}{2} \left(d \cos \frac{\pi}{3} - \theta - \cos \alpha \right) \end{aligned}$$

$$\begin{aligned} &= \frac{t_3}{2} \left(d \cos \frac{\pi}{3} + \theta - \cos \alpha \right) \\ &= \frac{t_4}{2} \left(d \cos \frac{\pi}{3} + \theta + \cos \alpha \right) \\ &= \frac{t_5}{2} \left(d \cos \frac{\pi}{3} - \theta + \cos \alpha \right) \\ &= \frac{t_6}{2} (d \cos \theta + \cos \alpha) \end{aligned}$$

The cross-sectional area of each bar is $\frac{r\pi D^2}{24}$. The total compressive force minus the total tensile force in the bars is

$$\begin{aligned} &\frac{r\pi D^2}{24} (t_1 + t_2 + t_3 - t_4 - t_5 - t_6) \\ &= \frac{r\pi D^2 mc}{24(1 - \cos \alpha)} \left(d \cos \theta - \cos \alpha \right. \\ &\quad \left. + d \cos \frac{\pi}{3} - \theta - \cos \alpha + d \cos \frac{\pi}{3} + \theta \right. \\ &\quad \left. - \cos \alpha - d \cos \frac{\pi}{3} + \theta - \cos \alpha \right. \\ &\quad \left. - d \cos \frac{\pi}{3} - \theta - \cos \alpha - d \cos \theta - \cos \alpha \right) \\ &= \frac{r\pi D^2 mc}{24(1 - \cos \alpha)} (-6 \cos \alpha) \\ &= \frac{r\pi D^2 mc \sin \phi}{4(1 + \sin \phi)} \quad \quad \quad (3) \end{aligned}$$

The moments of the forces in the bars about the centre of the section are

$$\begin{aligned} &\frac{r\pi D^2}{24} \left(t_1 \frac{dD}{2} \cos \theta + t_2 \frac{dD}{2} \cos \frac{\pi}{3} - \theta \right. \\ &\quad \left. + t_3 \frac{dD}{2} \cos \frac{\pi}{3} + \theta + t_4 \frac{dD}{2} \cos \frac{\pi}{3} + \theta \right. \\ &\quad \left. + t_5 \frac{dD}{2} \cos \frac{\pi}{3} - \theta + t_6 \frac{dD}{2} \cos \theta \right) \\ &= \frac{r\pi D^2 mc}{48(1 - \cos \alpha)} \left[(d \cos \theta - \cos \alpha) \cos \theta \right. \\ &\quad \left. + \left(d \cos \frac{\pi}{3} - \theta - \cos \alpha \right) \cos \frac{\pi}{3} - \theta \right. \\ &\quad \left. + \left(d \cos \frac{\pi}{3} + \theta - \cos \alpha \right) \cos \frac{\pi}{3} + \theta \right] \end{aligned}$$

$$\begin{aligned}
 & + \left(d \cos \frac{\pi}{3} + \theta + \cos \alpha \right) \cos \frac{\pi}{3} + \theta \\
 & + \left(d \cos \frac{\pi}{3} - \theta + \cos \alpha \right) \cos \frac{\pi}{3} - \theta \\
 & + (d \cos \theta + \cos \alpha) \cos \theta \Big] \\
 & = \frac{r\pi D^3 d m c}{24(1 - \cos \alpha)} \left[d \cos^2 \theta + d \cos^2 \frac{\pi}{3} - \theta \right. \\
 & \quad \left. + d \cos^2 \frac{\pi}{3} + \theta \right] \\
 & = \frac{r\pi D^3 d^2 m c}{48(1 - \cos \alpha)} \left(3 + \cos 2\theta + \cos \frac{2\pi}{3} - 2\theta \right. \\
 & \quad \left. + \cos \frac{2\pi}{3} + 2\theta \right) \\
 & = \frac{r\pi D^3 d^2 m c}{16(1 - \cos \alpha)} \\
 & = \frac{r\pi D^3 d^2 m c}{16(1 + \sin \phi)} \quad \quad \quad (4)
 \end{aligned}$$

Expressions (3) and (4) are both independent of the position and number of the bars in the group provided that there is an even number. This is only true if the modular ratio m , and not $m - 1$, is used in considering compressive stresses in the bars.

Since the total compressive force less the total tensile force in the section is equal to the load, expressions (1) and (3) together equal W , that is,

$$W = \frac{D^2 c Y}{4(1 + \sin \phi)} + \frac{r\pi D^2 m c \sin \phi}{4(1 + \sin \phi)}$$

Therefore

$$W = \frac{D^2 c (Y + r\pi m \sin \phi)}{4(1 + \sin \phi)} \quad (5)$$

From (5),

$$e = \frac{4W(1 + \sin \phi)}{D^2(Y + r\pi m \sin \phi)} \quad (5a)$$

Since the sum of the moments about the centre of the compressive forces added to the moments of the tensile forces is equal to M , expressions (2) and (4) together are equal to WeD , that is

$$WeD = \frac{D^2 c X}{96(1 + \sin \phi)} + \frac{r\pi D^3 d^2 m c}{16(1 + \sin \phi)}$$

$$\text{and } We = \frac{D^2 c \left(\frac{X}{24} + \frac{r\pi m d^2}{4} \right)}{4(1 + \sin \phi)} \quad (6)$$

Substituting the value of W from equation (5) in equation (6)

$$\begin{aligned}
 \frac{D^2 c (Y + r\pi m \sin \phi)}{4(1 + \sin \phi)} \times e \\
 = \frac{D^2 c \left(\frac{X}{24} + \frac{r\pi m d^2}{4} \right)}{4(1 + \sin \phi)}
 \end{aligned}$$

$$Y + r\pi m \sin \phi = \frac{X}{24e} + L \quad (7)$$

The curves in *Fig. 2* represent the left-hand side of equation (7) for values of r between its normal permissible limits of 0.008 and 0.08. The right-hand side of the equation is represented by a line plotted on the graphs for various values of ϕ . The co-ordinates of the point of intersection of the curve and the line give the solution of equation (7) for values ϕ on the horizontal axis and $Y + r\pi m \sin \phi$ on the vertical axis; these may be substituted in equation (5a). The maximum stress in the steel is found from the stress-variation diagram.

Prestressed Pile 192 ft. Long.

A PRESTRESSED concrete hollow pile 192 ft. long, 3 ft. outside diameter, and with a wall 4 in. thick has been driven in the Gulf of Mexico. The pile contained eight prestressing cables each comprising six wires, which were tensioned to 150,000 lb. per square inch and bonded to the concrete by the pre-tensioning method. The pile contained 9½ lb. of prestressing steel and 5 lb. of untensioned steel per foot. The pile passed through

37 ft. of water and penetrated 22 ft. into the mud under its own weight. It was driven by a single-acting hammer with a 12,500-lb. ram having a stroke adjustable to 24 in. or 39 in.; 4600 blows with a 24-in. stroke and 1000 blows with a 39-in. stroke were used. No difficulty was experienced in driving the pile with extended leaders on a frame used for driving shorter piles. This type of pile is patented by the Raymond Concrete Pile Company.

A Prestressed Bridge in the U.S.A.

PRECAST BEAMS WITH BONDED WIRES CAST ON THE SITE.

A PRESTRESSED precast concrete bridge now being built at Roseville, Ohio, U.S.A., is 220 ft. long and comprises five spans of 44 ft. The construction is unusual in that the beams are being cast on the site on a long-line process. The following description of the bridge is abstracted from the U.S.A. journal, "Engineering News-Record."

Each of the five spans consists of nine precast T-beams 30-in. deep and a cast-in-place deck slab bonded to the beams (Fig. 1). Beams were chosen in preference to a thick slab because the bridge

and transfer the prestressing force to the concrete by bond. It is assumed that when the tensioning force is removed the stress is about 147,000 lb. per square inch and that the effective stress will be 133,000 lb. per square inch after shrinkage and creep of the concrete have taken place. The stress in the concrete in the bottom flange is 2000 lb. per square inch when the tensioning force is removed and 1600 lb. per square inch ultimately. The crushing strength of the concrete is at least 5000 lb. per square inch when the prestressing force is removed. The pre-




Fig. 1.—Beams in Position ready for Concreting the Deck.

is on a 45-deg. skew and because headroom is not an important consideration. The span-depth ratio of the beams is 18 to 1. To reduce the amount of shuttering required for the deck, the beams are placed with the top flanges 8 in. apart. Concrete is cast to a depth of at least 4½ in. over the beams and also fills the spaces between the top flanges, making the total depth of the deck 7½ in. Dowels extend from the sides and top of the flanges into the deck to ensure transfer of the shearing forces between the precast and cast-in-place components (Fig. 2).

The prestressing force is applied to each beam by thirty-two ¼-in. diameter cables, each composed of seven strands with an area of 0.0352 sq. in. The cables have an ultimate tensile strength of 260,000 lb. per square inch and were tensioned to 160,000 lb. per square inch. They are placed in the bottom flange

stressing force may create tensile stresses in the top flange, but these are limited to half the modulus of rupture of the concrete. Despite the low tensile stresses, nominal reinforcement is incorporated in the top flange. Under the design load there will be no tensile stresses in the bottom flange and at the same time the compressive stress in the deck or in the top flanges of the beams is less than 600 lb. per square inch. Lower strength concrete may therefore be used for the deck than for the beams. The concrete in the deck slab has a crushing strength of at least 4000 lb. per square inch at 28 days, with a slump not exceeding 2½ in. The leaner mixture is expected to reduce shrinkage of the deck. The maximum shearing stress in a beam will not exceed 200 lb. per square inch and nominal stirrups only, comprising one ¾-in. bar every 12 in., are used.

The beams in each span are prestressed transversely with four 0-6-in. diameter 7-strand cables, with an area of 0.215 sq. in. These are tensioned to 125,000 lb. per square inch and extend through two cast-in-place diaphragms between the beams, and transfer the prestressing force through end anchorages. The diaphragms are parallel to the bridge piers and abutments.

Casting the Beams.

The casting yard is a concrete road 16 ft. wide at the site and, although the road curves, there is sufficient length for a stressing bed 145 ft. long. Two parallel lines are used in each of which three beams can be cast. The procedure is (1) Tension the cables; (2) Place the shutters; (3) Cast the concrete; (4) When the concrete has attained a strength of at least 5000 lb. per square inch, cut the wires between the beams with a flame; (5) Move the beams into place on to the piers and abutments.

To resist the tensioning force of 160,000 lb. applied to the 32 cables in each beam, concrete abutments, 4 ft. high by 4 ft. thick, were built across the road at both ends of the stressing bed (Fig. 3).



Fig. 3.—An Abutment.

They transmit the horizontal thrust to the road slab, and overturning is resisted by five piles.

The cables are prepared on a bench 145 ft. long. Each cable is about 600 ft. long, that is somewhat longer than four times the length of the stressing bed. Sleeves for anchoring a cable after tensioning are pressed on the free ends with an hydraulic tool. The cable is looped to form four lengths of about 150 ft. each. The looped ends of one cable are inserted in slots in one face of a steel block 4 in. thick. A similar cable is then placed in slots in the opposite face of the block. At the other end the free ends of the cables are attached




Fig. 2.—Details of the Beams and the Temporary Anchor-blocks.

to a block by the anchoring sleeves and the looped end is inserted in a slot (Fig. 2).

The blocks are used to tension eight lengths of cable simultaneously, thus reducing the number of temporary anchorages from 64 to 16 per production line.

After the cables are assembled they are moved to the stressing bed, the blocks being held in position by steel guides in the abutments. Pulling rods, 1 in. diameter, attached to each anchorage block, are then fastened to a 30-tons jack and the strands stretched until a gauge indicates that the required force has been applied. The steel has then elongated $12\frac{1}{2}$ in. Steel shims are inserted between the anchorage blocks and a steel bearing-plate in the abutment to maintain the extension.

Three sets of plywood shutters, one for each beam in a production line, were designed to be used fifteen times. They are in short lengths for easy handling, and are put in place rapidly, after which all the reinforcement bars, dowels, and stirrups are inserted (Fig. 4).

The concrete contains 705 lb. of air-entraining cement per cubic yard with an addition of one per cent. of calcium chloride. The strength at seven days exceeds 5000 lb. per square inch. The shutters are stripped within two days, and the concrete is cured for five to seven days. The wires are cut a few cables at a time throughout the length of the line, to reduce movement of the beams when the force is released.




Fig. 4.—Shuttering for Beams.

Transverse Prestressing.

The cables for transverse prestressing are passed through holes in the beams, and wrapped with paper to prevent bond with the cast-in-place concrete of the diaphragm. The diaphragms and the deck are concreted simultaneously and, when the concrete has attained sufficient strength, the transverse cables are tensioned and anchored at their ends by tightening a nut on swaged fittings.

The bridge was designed and constructed by Messrs. Wander and Mason, Inc., of Worthington, Ohio, and the design was checked by Messrs. Alden E. Stilson and Associates, consulting engineers for the Board of Commissioners of Muskingum County, Ohio.

"Popcorn" Concrete.

In this country concrete containing no sand is known by the somewhat unfortunate term "no-fines" concrete. In Holland, where it originated early this century, it was known as "Korrelbeton" because it resembled coral. In a paper read at a recent convention of the American Concrete Institute, Professor George

W. Washa, chairman of the Lightweight Concrete Committee of the Institute, describes it as popcorn concrete. It is a pity that when the process was copied from Holland it should have been thought necessary to use a different term, for coral concrete is a better and more properly descriptive term than either no-fines or popcorn.

Tests on Lightweight Prestressed Beams.

TESTS on prestressed concrete made with expanded shale have been made by the Carter-Waters Corporation of Kansas City and Prestressing, Inc., of San Antonio, Texas, U.S.A. The beams were 32 days old when they were tested.

The first tests were made on the beam shown in Fig. 1. The concrete consisted of 635 lb. of cement, 1.1 cu. yd. of aggregate, and 50.5 U.S. gallons (42 Imperial gallons) of water, which when mixed together made one cubic yard of concrete with a density of 105 lb. per

were bonded with cement grout and the other had unbonded cables.

The first tests consisted of applying loads at third points, measuring the deflections, and taking strain-gauge readings. The five loads applied were (1) 70 per cent. of the design load, (2) 125 per cent. of the design load, (3) loading the beam until it cracked, (4) loading the beam until it cracked across the whole of the middle third of its length, and (5) loading until the beam broke. The beam was allowed time to recover from one




Fig. 1.

cubic foot and a compressive strength (tested as cylinders) of 6,000 lb. per square inch at 28 days. A total prestressing force of 113,500 lb. was applied by sixteen 0.25-in. diameter wires with a yield strength of 183,000 lb. per square inch. The beam was designed to carry a load of 19,500 lb.

For the second series of tests two beams were made, each similar to that used in the first test except that the thickness of the webs was 5 in. and the width of the flanges 11 1/2 in. The prestressing force in each beam was 127,800 lb. and the design load 26,600 lb. In one beam the cables

application of the load before the next was made.

In the second series of tests, the two beams were loaded against each other through a system of two screw-jacks and two coil-springs. The design load was applied to each beam and allowed to remain for 121 days. The prestressing force in the beams was determined at intervals during this period. After this test each beam was tested separately to destruction.

From the tests it is concluded that

(1) The strength of the concrete was adequate for prestressing.

(2) The modulus of elasticity of the concrete was sufficiently high for prestressing. Reductions of the modulus of elasticity when the beams were loaded for a long period were not excessive, and when the load was removed and then reapplied the beams recovered a sufficiently high modulus of elasticity. The moduli of elasticity were as follows. In the first tests: At the time of loading, 3.24×10^6 lb. per square inch; after a load of 70 per cent. of the design live load had been applied for 46 hours, 2.85×10^6 lb. per square inch. After a load of 1.25 times the design load had been removed the modulus apparently recovered to 3.15×10^6 lb. per square inch. In the second tests: At the time of loading, 3.38×10^6 lb. per square inch; after two days of loading, 2.75×10^6 lb. per square inch; after 121 days, 1.73×10^6 lb. per square inch; when the load was removed the modulus recovered to 2.31×10^6 lb. per square inch.

(3) The losses of the prestressing forces due to shrinkage and creep were not excessive and an allowance of 25 per cent. loss of the initial prestressing force is thought to be satisfactory. The actual losses were calculated from the results of the 121 days' test as 19 per cent. for the beam with ungrouted cables and 17 per cent. for the beam with bonded cables.

(4) The beam with bonded wires broke when the load was 59,900 lb. and the beam with unbonded wires at 44,000 lb. The load at which cracks first appeared was slightly higher in the case of the bonded wires.

(5) Lightweight concrete behaves elastically for loads of up to the design load.

The foregoing notes are based on an article by Mr. Fred E. Koebel in the *Journal of the American Concrete Institute* for March, 1954.

Patent Relating to Concrete.


A Device for Tensioning Wires.

In a device (Figs. 1 and 2) for tensioning a number of wires simultaneously, a force is applied to a primary bridge member (4) at a point between its ends and thence from each end of the member to a point between the ends of each of a pair of sub-bridge members (18), and from the ends of each member (18) to the separate wires. The member (4) is pivotally connected at its centre to a bolt (1) and at each end pivotally supports a link (7)

which is pivotally connected to the centre of one of the members (18). To each end of each member an anchor for a wire is pivotally connected. Each anchor has a spring-loaded serrated jaw (13) which may be locked in an open position. A force applied to the bolt (1), by an hydraulic jack for example, is applied equally to the wires held by the four anchors. To anchor the wires in the jaws a pin is used to lock the bolt (1) to the bridge (4) and wedges prevent movement of members (18).

The device is modified for use with three wires by arranging the members (18) parallel to the bridge (4), connecting the links (7) so that the outside arm of each member (18) is twice the length of the inside arm, and joining the two inside arms to a common anchor. Unequal forces may be applied to the wires by pivoting the bridges, and the device may be modified for tensioning more than four wires.—No. 657,794. Minister of Works. February 4, 1949.

[Publication of Patent Specifications is in arrears due to the war.]



Eccentrically-loaded Columns.

THE results of an investigation of the behaviour of eccentrically-loaded reinforced concrete columns are given in a report entitled "A Study of Combined Bending and Axial Load in Reinforced Concrete Members," by Eivind Hognestad (University of Illinois Engineering Experiment Station, Bulletin No. 399). A total of 120 columns were loaded to failure in short-time tests, the period between the first and last increments of load being about one hour. The columns were divided into four groups, each of thirty columns. The sizes of the columns and the amounts of reinforcement are shown

supports of the columns except for the concentrically-loaded helically-reinforced columns which were tested with flat ends. All the columns were cast in a vertical position and they all failed in the upper half; this was considered to be due to variations in the strength of the concrete from the bottom to the top of a column due to differences in the compaction. Electrical-resistance strain-gauges were used to measure the strains in the reinforcement and near the surface of the concrete; the lateral deflections of the columns in the plane of the eccentricity were also measured.




Fig. 1.—Details of Columns.

in Fig. 1. Within each group the strength of the concrete at 28 days varied from 1500 lb. to 5500 lb. per square inch. The longitudinal reinforcement comprised deformed bars with an average yield stress of about 43,500 lb. per square inch, the rectangular hoops were $\frac{1}{4}$ -in. bars with a yield stress of about 60,000 lb. per square inch, and the helical binding was hard drawn wire of about $\frac{1}{4}$ in. diameter with an average ultimate tensile stress of about 115,000 lb. per square inch. The columns were tested in a machine with a capacity of 3,000,000 lb. The eccentricity of the load was varied from 0 to $1\frac{1}{4}$ times the lateral dimension of a column and the load was applied through "knife-edges" at the top and bottom

Loads Causing Failure of Rectangular Columns.

The ultimate loads on the columns of groups I, II and III are shown in Figs. 2, 3, and 4, which show also the ultimate loads calculated by the theories due to Mr. Whitney, Mr. Jensen, and the author.* The eccentricities shown on these graphs are the initial eccentricities of the loads plus the deflections at failure measured with respect to the knife-edges through which the loads were applied.

In agreement with the findings of earlier investigators, it was found that the ultimate loads for columns loaded concentrically through knife-edges were 10 to 15 per

* See references on page 308.




Fig. 2.—Loads at Failure, Group I.




Fig. 3.—Loads at Failure, Group II.




Fig. 4.—Loads at Failure, Group III.




Fig. 5.—Loads at Failure, Group IV.

cent. lower than for similar columns tested with flat ends. This is explained as being due to the difficulty of obtaining a truly concentric application of load through knife-edges. The failure of all eccentrically-loaded rectangular columns was caused by crushing of the concrete at an ultimate strain of about 0.0038. After such crushing had taken place, the reinforcement in compression buckled between the ties, and the strength of the columns was thereby reduced very considerably. The reinforcement in compression in most cases yielded before failure of the concrete. Preceding the failure of the concrete, all eccentrically-loaded columns were in a state of equilibrium with the applied load such that there were considerable increases in deformation for very small additions of load. Columns which failed in tension developed much larger deflections before final crushing of the concrete than did the columns that failed in compression. A fairly linear distribution of strains across the column existed from the smallest loads to failure.

Loads Causing Failure of Helically-reinforced Columns.

The loads causing failure of the helically-reinforced columns are shown in Fig. 5 in the same manner as for the rectangular columns.

The concentrically-loaded columns were loaded with flat ends. Their general behaviour was in agreement with the findings of earlier investigators. After the cover spalled the columns continued to deform; by the action of the helical reinforcement, a higher load was carried than that causing spalling.

The ultimate load of the eccentrically-loaded columns, which were loaded through knife-edges, was, however, reached at failure of the concrete cover. After failure of the cover, all the eccentrically-loaded columns developed extremely large deflections without serious decreases in load-carrying capacity, since the binding prevented buckling of the longitudinal reinforcement and crushing of the concrete core. Regardless of the eccentricity of load, the columns were able to carry fairly high loads and deform very considerably.

Calculation of the Loads Causing Failure.

The Bulletin contains an historical review of the methods of calculating the ultimate load which a reinforced concrete member will resist, and in particular the author compares the methods due to Mr. Whitney and Mr. Jensen with the results of the tests, on the basis of which the following theory was developed.

The distribution of stress and strain across a rectangular member was assumed to be as shown in Fig. 6(a), in which the notation not obvious from the diagram is: f'_c , compressive strength of cylinders 6 in. diameter by 12 in. high; f_{yp} , yield stress of the reinforcement in compression; A_s' , area of steel in compression; C' , total compressive force in the steel; C , total compressive force in the concrete; f'_e , compressive strength in bending of concrete (assumed to be 0.85 f'_c); b , width of the column; k_1 and k_2 , constants defining the area of the stress-diagram and its centre of gravity; ϵ , ultimate strain of the concrete in bending.

From Fig. 6(a), and calculating moments about the steel in tension,

$$Pe' = k_1 b c f'_e (d - k_2 c) + A_s' f_{yp} d' \quad (1)$$

Also

$$P = k_1 b c f'_e + A_s' f_{yp} - A_s f_s \quad (2)$$

and

$$f_s = \epsilon E_s \frac{d - c}{c} < f_{yp} \quad (3)$$

The notation is as previously defined, except for E_s which is the modulus of elasticity of the steel and f_{yp} the yield stress of the steel in tension.

Failure in tension starts by yielding of the steel in tension; this produces a movement of the neutral axis towards the edge of the section which is compressed, and the ultimate load is reached when the compressed concrete crushes. At failure $f_s = f_{yp}$, and from (1) and (2)

$$P = f'_e b d \left[q' - q + \frac{1}{2\alpha} \left\{ - \left(\frac{e'}{d} - 1 \right) + \sqrt{\left(\frac{e'}{d} - 1 \right)^2 + 4\alpha \left[q' \frac{d'}{d} + \frac{e'}{d} (q - q') \right]} \right\} \right] \quad (4)$$

in which $q' = \frac{A_s' f_{yp}}{b d f'_e}$,

$$q = \frac{A_s f_{yp}}{b d f'_e}, \text{ and } \alpha = \frac{k_2}{k_1}$$

Equation (4) may be simplified as follows for symmetrical reinforcement,

$$q' = q :$$

$$P = f_c'' b d \left[- \left(\frac{e'}{d} - 1 \right) + \sqrt{\left(\frac{e'}{d} - 1 \right)^2 + 4 \frac{q}{d}} \right] \quad (5)$$

When there is no compressive reinforcement, $q' = 0$, and

$$P = f_c'' b d \left[-q + \frac{1}{2\alpha} \left[- \left(\frac{e'}{d} - 1 \right) + \sqrt{\left(\frac{e'}{d} - 1 \right)^2 + 4 \frac{q}{d}} \right] \right] \quad (6)$$

The values of k_1 and k_2 vary with the compressive strength of the concrete but their ratio α is very nearly constant and has a value of 0.55.

Failure in compression will take place if the compressed concrete fails before the steel in tension yields. The stress in

the tensile steel must therefore be calculated from (3). The calculation of P may then be made from (1) and (2), and as their solution involves a cubic equation it may best be carried out by iterative or graphical methods.

The limiting condition at failure in which the steel in tension yields as the concrete crushes (known as the balanced condition) can be defined in terms of

$k = \frac{c}{d'}$, indicating the position of the

neutral axis at failure. For the balanced

condition this ratio is $k_b = \frac{e_u}{e_u + \frac{f_{yp}}{E_s}}$.

Failure in tension will occur if $k < k_b$, and failure in compression will result if

$k > k_b$. By introducing $k_b = \frac{c_b}{d}$ into (1)

and (2) the eccentricity causing balanced failure and the corresponding ultimate load may be calculated.

If the eccentricity is small the neutral axis will be outside the section, and from




Fig. 6.—Rectangular Columns.

August, 1955.




Fig. 7.—Circular Columns.

Fig. 6(b) equations (1) and (2) are modified to

$$Pe' = k_1 f_c'' bc(d - k_2 c) + A_s' d' f_{yp}' + Abx \quad (1a)$$

$$P = k_1 f_c'' bc + A_s' f_{yp}' - A_s f_s - Ab \quad (2a)$$

in which A and x may be found by geometry.

In the case of circular sections (Fig. 7) an equivalent uniform distribution of stress is assumed over a segment with a rise $k_1 c$, and the author assumed that the values of k_1 for a rectangular section could be used as an approximation. The resultant compressive force in the concrete was assumed to act at the centroid of the segment, the distance x from the centre of the section to the centroid of the section being expressed approximately, according to Mr. Whitney, as

$$\frac{x}{D} = \frac{2}{3\pi} + 0.293 \left(\frac{\pi}{4} - \frac{2A}{D^2} \right)$$

in which A is the area of the segment.

The following equations apply to failures by both tension and compression and, from Fig. 7, by the equilibrium of forces,

$$P = 0.85 f_c' A + E_s \Sigma A_s \epsilon_s \quad (7)$$

From the equilibrium of moments,

$$Pe = 0.85 f_c' A x + E_s \Sigma A_s \epsilon_s x_s \quad (8)$$

By geometry,

$$\left. \begin{aligned} \epsilon_{s1} &= \frac{\epsilon_u}{c} \left(\frac{D}{2} + x_{s1} - e \right) \\ \epsilon_{s2} &= \frac{\epsilon_u}{c} \left(\frac{D}{2} + x_{s2} - e \right) \\ \epsilon_{s1}' &= \frac{\epsilon_u}{c} \left(e - \frac{D}{2} + x_{s1} \right) \\ \epsilon_{s2}' &= \frac{\epsilon_u}{c} \left(e - \frac{D}{2} + x_{s2} \right) \end{aligned} \right\} \quad (9)$$

Because of the assumed trapezoidal distribution of stress to strain for the reinforcement,

$$\epsilon_s < \frac{f_{yp}}{E_s} \quad (10)$$

the condition referred to as balanced failure will exist if, at the ultimate load,

$$e = \frac{\epsilon_u}{\epsilon_s + \frac{f_{yp}}{E_s}} \left(\frac{D}{2} + x_{s1} \right) \quad (11)$$

Graphs plotted from these formulae are shown in Figs. 2 to 5 in relation to the observed ultimate loads for the columns tested.

REFERENCES.

- Jensen, V. P., "Ultimate Strength of Reinforced Concrete Beams as Related to the Plasticity Ratio of Concrete," University of Illinois Engineering Experiment Station Bulletin No. 345, June 1943.
- Whitney, C. S., "Design of Reinforced Concrete Members Under Flexure and Combined Flexure and Direct Compression," A.C.I. Journal, March-April 1937; Proceedings Vol. 33, pp. 483-98.
- Whitney, C. S., "Eccentrically Loaded Reinforced Concrete Columns," Concrete and Constructional Engineering, Vol. 33, No. 11, Nov. 1938, pp. 549-61.
- Whitney, C. S., "Application of Plastic Theory to the Design of Modern Reinforced Concrete Structures," Journal of the Boston Society of Civil Engineers, Vol. 35, No. 1, Jan. 1948, pp. 39-53.
- Whitney, C. S., "Plastic Theory in Reinforced Concrete Design," Proceedings A.S.C.E., Dec. 1940; Transactions A.S.C.E., Vol. 107, 1942, pp. 251-326.

Heating Coils in Concrete Floors.

THE hot-water heating system installed in the floors of a block of residential flats 14 stories high at Chicago is described by the American Heating, Piping and Air-conditioning Contractors' Association. The system is designed to produce a comfortable temperature inside the building when the outdoor temperature is -10 deg. Fahr. The coils are of copper tube of $\frac{1}{2}$ -in. outside diameter, and are placed $\frac{1}{4}$ in. from the bottom of reinforced con-


crete floor slabs 7 in. thick. Water is supplied from a tank on the roof at a temperature of 175 deg. Fahr. and returned at 145 deg. Fahr.; the average temperature in the coils is 160 deg. Fahr. About two-thirds of the heat is directed downwards through the ceiling and the remainder upwards through the floor above. It is claimed that this method is cheaper than other means of heating blocks of residential flats.

"Ritecure"

THE RIGHT CURE FOR CONCRETE

MEMBRANE CURING for all concrete construction

from 36,000
sq. yds➔



Apron and Link Road.

to 3,500,000
sq. yds➔



Photograph by courtesy of Air Ministry. Contractors: Messrs. John Laing & Son, Ltd.

Over 18,000,000 sq. yds. of concrete cured in this country with "Ritecure." The proved economical efficiency of "Ritecure," ease of application, drastic reduction of labour costs, and the assurance of complete curing under any climatic condition, make this material the supreme answer to all concrete curing requirements. "Ritecure" is backed by 32 years of practical experience in the field of civil engineering and public works construction. For full details, test reports, and technical advice, etc., write to

STUART B. DICKENS, LTD.

36 VICTORIA STREET,

WORKS: OLD MILTON STREET

LONDON, S.W.1.

LEICESTER.

TELEPHONE: ABBEY 4930

TELEPHONE: LEICESTER 30800

MOULDS

for post-tensioned
prestressed
concrete units

Consult



**the most comprehensive
mould service in the world**

**EXPERTS IN THE DESIGN AND PRODUCTION OF
SPECIALISED MOULDS FOR PRECAST CONCRETE**

**PRESTRESSED CONCRETE CONGRESS
AMSTERDAM, AUG. 29 - SEPT. 2**

Stelmo Moulds for prestressed concrete work will be on show at the International Congress on Prestressed Concrete, together with full details of the STELMO MOULD SERVICE. Technical advice on all matters relating to moulds for all purposes in precast concrete work will also be available.

Recent contracts carried out by us include the supply of moulds for the production of precast concrete units for bridges and schools. These moulds called for a high degree of accuracy both in shape and dimensions, and the correct position of cores for the prestressing cables. Careful study of our customers' requirements enabled us to design and supply moulds which met with their full approval.

USE OUR SERVICE NOW

STELMO, LTD., BETHWIN ROAD, LONDON, S.E.5. Telephone: Rodney 5981

New System of Prestressed Floor Construction.

THE first floor of a two-story extension at the Plastool factory at Fooks Cray, Kent, is designed to carry fairly heavy machinery which is liable to excessive wear as a result of vibration, and it was required to distribute the concentrated loads in both directions with as little deflection as possible. The area of the floor is 590 sq. yd., and the design load 200 lb. per square foot plus 18 lb. per square foot for finishes. A Raphcon pre-

tudinally to form a continuous slab with bays of 16 ft. 4 in., 11 ft. 6 in., and 16 ft. 4 in. (see *Figs. 1 and 2*).

In constructing this type of floor three or five short lightly-reinforced units are arranged in line in each span, supported on temporary props, with gaps of 4 in. to 6 in. between their ends (*Fig. 2*). Prestressing wires are placed on either side on the units, and steel reinforcement placed transversely over the prestressing




Fig. 1.

stressed precast floor, as shown in the accompanying illustrations, was used. These floors are made with either hollow units the wires in which are pre-tensioned, or hollow reinforced units that are prestressed by the post-tensioning method. The precast units are made on a collapsible core which can be adapted to form units from 5 in. to 10 in. deep by 12 in. to 15 in. wide, suitable for spans of 16 ft. to 40 ft., preferably arranged in two, three, or four bays to allow for continuous spans. The units are prestressed longi-

tudinally to form a continuous slab with bays of 16 ft. 4 in., 11 ft. 6 in., and 16 ft. 4 in. (see *Figs. 1 and 2*).

With a smaller central span, as in this example, the load on the outer bays can cause a negative bending moment on the central span, which would produce tensile stresses in the top. Some of the prestressing wires are therefore arranged in both the top and bottom of the central span, but they are all in the bottom of the outer bays in order to produce compression to counteract any tension caused by any combination of loading. The gaps



333 Simplex Cast-in-situ Concrete Piles were used in the foundations of the Municipal College Extensions in Anglesey Road, Portsmouth

Architect to the City of Portsmouth: F. Mellor, Esq., F.R.I.B.A.

Write for Illustrated Brochure

SIMPLEX CONCRETE PILES LTD.

25 BRECHIN PLACE,

SOUTH KENSINGTON,

LONDON, S.W.7

Telephone: Fremantle 0035-6



*Some views of the open-air swimming pool at the Skegness Holiday Camp.
By kind permission of Messrs. Butlins Ltd.*



waterproofing concrete with Sternson No. 300

Practical experience on a large number of water-containing structures has proved that STERNSON NO. 300 provides the most dependable means of obtaining a dense and impermeable concrete which will resist heavy water pressures. The list of important contracts on which STERNSON NO. 300 has been specified includes Swimming Pools, Factories, Harbour work, and underground structures of all types, and cement renderings on housing estates, etc. STERNSON NO. 300 is an integral waterproofer which can be used with confidence for all forms of concrete construction, and for providing a waterproof rendering for existing concrete and brick surfaces. STERNSON NO. 300 is a water repellent. It increases the tensile and crushing strengths without retarding the setting action. It increases the workability of the mix, thus permitting lower water-cement ratios. Full technical information on STERNSON NO. 300, and expert advice on all concrete waterproofing problems, are available on request.

STUART B. DICKENS, LTD.

36 VICTORIA STREET,
WORKS: OLD MILTON STREET

LONDON, S.W.1.
LEICESTER,

TELEPHONE: ABBEY 4980
TELEPHONE: LEICESTER 20390




Fig. 3.—Anchor Blocks.




Fig. 4.—Tensioning the Wires.




Fig. 5.—Cables anchored to Reinforcement of Edge Beam.

between the units are then concreted to form continuous beams.

At one end of the floor the wires pass around a semi-circular anchorage (*Fig. 3*) similar to that used in some German systems, and at the other end they are tensioned by a jack (*Fig. 4*) bearing against a precast reinforced concrete block. The wires may be tensioned from one end or alternate ends. Alternatively the prestressing wires may at the anchorage end pass around the reinforcement of an edge-beam (*Fig. 5*), and be tensioned after the edge-beam has been concreted in situ.

After prestressing, the floor is fully suspended and continuous before the spaces between the beams are concreted; services can therefore be installed before the beams are concreted together. No topping is required structurally. The floor acts as a monolithic slab over the three bays, and has about one-fifth of the deflection of a simply-supported slab.

The architect is Mr. V. A. Asbridge, A.R.I.B.A., and the contractors the Vibrated Concrete Construction Co., Ltd., who manufactured the units in conjunction with Raphcon, Ltd.

Consolidating Granular Soil.

A METHOD of consolidating sand or gravel soils by wetting and vibration was used in Germany some twenty years ago. It has been used in the United States of America for the past ten years, and is now available in this country. The process is a method of consolidating columns of such soils up to depths of 50 ft. and diameters of 10 ft. and so increase their load-bearing properties.

The apparatus (*Fig. 1*) is suspended from a crane, and the process is as follows (from left to right in *Fig. 2*). (1) The vibrator is started and the bottom jet is opened to saturate the soil for the vibrator to penetrate; (2) With the jet open, the machine is allowed to sink into the soil by its own weight; because of the vibration and upward movement of the water, a "quick" condition is produced which enables the vibrator to descend rapidly. (3) Compaction of the soil surrounding the vibrator takes place and a cone-shaped crater about 3 ft. diameter is formed at ground level. When the machine has reached the desired depth, the water is delivered from the top jets. The amount of water issuing from these openings is much less than that supplied from the bottom jet and its downward flow helps to carry the sand along the sides of the machine to the bottom of the hole. The combined action of the vibration and the downward



Fig. 1.—Vibrator Suspended from a Crane.

flow of water compacts the soil and, as compaction takes place, additional sand is shovelled in at the top to compensate for the loss of volume caused by the increased density of the soil. (4) Actual compaction takes place during the intervals between the 1-ft. lifts which are made in returning the machine to the





Fig. 2.—Stages in the Process.




SMITH'S

FIREPROOF FLOORS


- The most adaptable System of Suspended Hollow Concrete Floor and Roof Construction for large and small spans.



Showing Two-Way Reinforcement and Hollow Concrete Blocks laid on Trianco Telescopic Centers.



Smith's Two-Way Reinforced Floor for distribution of point loads with efficiency and economy.



Illustrating the continuous Soffit with natural Key to which plaster readily adheres without hacking or other preparation to form finished ceiling.

**2 WAY REINFORCED
SUSPENDED
CONCRETE FLOORS**


Midland Associated Company & Licensees

**PARKFIELD CONCRETE PRODUCTS
COMPANY LIMITED**

St. Peter's Road
**NETHERTON, Nr. DUDLEY
WORCS.**

'PHONE : DUDLEY 4315

SMITH'S FIREPROOF FLOORS LTD
IMBER COURT • EAST MOLESEY • SURREY
EMBerbrook 3300 (4 lines)



IN ROOFS, WALLS, FLOORS, STAIRS

You get
greater strength
with less cement
when you use

WIREWELD

REINFORCEMENT

WIREWELD reinforcing fabric *in* the floors means less thickness *of* the floors and greater loads *on* the floors. With greater flexibility of planning and more space for use, WIREWELD represents both an initial and cumulative economy.

Easy to handle, and ready at various depots for immediate delivery, WIREWELD high-tensile fabric offers contractors the service they want—the right material, at the right price, at the right time !

A PRODUCT OF TWISTEEL REINFORCEMENT LTD.

LONDON: 43 UPPER GROSVENOR STREET, W.1 (GROSVENOR 1216) **BIRMINGHAM:** ALMA STREET, SMETHWICK, 40 (SMETHWICK 1991)

MANCHESTER: 7 OXFORD ROAD, MANCHESTER, 1 (ARDWICK 1691) **GLASGOW:** 19 ST. VINCENT PLACE, GLASGOW, C.1 (CITY 6954)

surface. The vibrator operates at the bottom of the hole until the desired density around the lower part of the machine is attained, and by raising the vibrator step by step and backfilling simultaneously the entire depth of soil is compacted. The machine is used at centres of 6 ft. to 10 ft. apart so that the columns of compacted soil overlap. While the machine is working the density

of the soil being compacted is recorded by an electrical device.

The consumption of water is 60 gallons a minute at a pressure of about 70 lb. per square inch. The weight of the apparatus for a penetration of 12 ft. is 2 tons. The licensees for the process in Great Britain and some other countries are Vibrofound, Ltd., of Southall, Middlesex.

A Tunnel in Scotland.

NEW ROCK-REMOVAL CAR.

THE accompanying illustrations show the method of driving a tunnel at Allt-na-Lairige, Argyll, for the North of Scotland Hydro Electric Board in connection with a new hydro-electric works. The tunnel will convey water a distance of 6600 ft. through a hill. It is 8 ft. high by 6 ft. 6 in. wide and is driven through granite. The small cross section and the nature of the rock made an advance of more than 8 ft. per cycle unlikely, but it was decided to attempt a higher speed. The air pressure used was 115 lb. per square inch at the face, and three Holman "Silver 3" hand drills were used to drill 21 holes in the pattern shown in Fig. 1. At the completion of the tunnel each machine had drilled about 30,000 ft. Tungsten-carbide tipped drills of $\frac{7}{8}$ -in. hexagonal section with $1\frac{1}{4}$ -in. diameter bits were used. To avoid loss of time in changing, drills 8 ft. long were used, and they had an average




Fig. 2.—The Shovel.




Fig. 1.—Pattern of Drilling.

"life" of about 300 ft. The 8-ft. holes were drilled in just over four minutes and the drilling speed (including time for moving from hole to hole) was 18 in. to 20 in. per minute throughout the work. The total drilling time was thus less than 35 minutes per cycle.

Broken rock was loaded with an Eimco Model 21 "Rockershovel" (Fig. 2). The width of the tunnel prevented any possibility of fast car-changing, and a special shuttle-car was used to ensure continuous loading. The general arrangement of this car is shown in Fig. 2 and



Fig. 3.—Arrangement of Rock-removal Car.



Fig. 4.—The Locomotive and Part of the Rock-removal Car.

photographs are given in *Figs. 4 and 5*. The main frame is 70 ft. long and is carried on two 8-wheel bogies. The chassis is supported on stub-axes integral with the frame of the bogie. The floor consists of a steel-slat conveyor-belt on rollers, propelled by hydraulic rams, which move back the loaded rock to make room for more. The rock moved as a rectangular mass about 3 ft. deep between the sides, which are 4 ft. 6 in. apart. The load was

negotiated. It was pulled by a modified 38-h.p. Diesel locomotive supplied by Messrs. F. C. Hibberd & Co., Ltd., who also collaborated in designing the controls, which could be operated from the loading end of the car 70 ft. away.


Twelve-hour shifts were worked by nine men, comprising a foreman, three drillers, two mechanics, one loader operator, one loco. driver, and one handy man. During the seven days from March 31 last, despite the loss of more than a shift in rectifying minor faults in the car, 67 cycles were completed, and the tunnel was driven 444 ft., which is thought to be a record. The consulting engineers are Messrs. Babbie, Shaw & Morton, and the contractors Messrs. Marples, Ridgway and Partners, Ltd.



Fig. 5.—Discharging the Rock.

discharged (*Fig. 5*) through the bottom of the car at the rear into tubs of 2 cu. yd. capacity. With the use of this car the time of clearing the rock after each drilling cycle was reduced from 80 minutes to 40 minutes.

The car travelled on a track of 2 ft. gauge with 30-lb. rails, and curves of a minimum radius of about 120 ft. were



MAKE IT A *FAST* JOB WITH MILLFRAMES



Horizontal tube inserted in Millframe Coupler. Half-turn the spring steel plate, tighten bolt—it's fast!

Going up. The next Millframe slides quickly into position on verticals of the H-FRAME below.

Half-turn plate, tighten bolt. Millframes are then secured to give standard lift height of 6'.

Millframes of special light-gauge steel tube give high speed erection and dismantling.

MILLS SCAFFOLD CO. LTD.

(A Subsidiary of Guest, Keen and Nettlefolds, Ltd.)

Head Office: TRUSSLEY WORKS, HAMMERSMITH GROVE, LONDON, W.6. (Riverside 5026/9)

Agents and Depots: BELFAST • BIRMINGHAM • BOURNEMOUTH • BRIGHTON • BRISTOL • CANTERBURY • CARDIFF
COVENTRY • CROYDON • DUBLIN • GLASGOW • HULL • ILFORD • LIVERPOOL • LOWESTOFT • MANCHESTER
NEWCASTLE • NORWICH • PLYMOUTH • PORTSMOUTH • READING • SHIPLEY • SOUTHAMPTON • SWANSEA • YARMOUTH

MISCELLANEOUS ADVERTISEMENTS.

Situations Wanted, 3d. a word : minimum, 7s. 6d. Situations Vacant, 4d. a word : minimum, 10s. Other miscellaneous advertisements, 4d. a word : 10s. minimum. Displayed advertisements, 30s. per column inch. Box number 1s. extra. The engagement of persons answering these advertisements is subject to the Notification of Vacancies Order, 1952.

Advertisements must reach this office by the 23rd of the month preceding publication.

SITUATIONS VACANT.

SITUATIONS VACANT. THE TRUSSED CONCRETE STEEL CO., LTD., have vacancies in their London, Birmingham, Glasgow, and Manchester offices for reinforced concrete designers and detailers. Five-days' week. Pension scheme. Apply, giving full particulars of age, education, and previous experience, to the SECRETARY, Truscon House, 35-41 Lower Marsh, London, S.E.1.

SITUATIONS VACANT. Reinforced concrete designer-draftsmen required by ASHMORE, BENSON, FRASE & CO., Stockton-on-Tees. Applicants should be fully experienced in either designing or detailing reinforced concrete structures, foundations and other civil work. Maximum assistance given in obtaining accommodation, pension scheme, technical library, and sports facilities available. Apply, stating age, experience, etc., quoting reference "D" to STAFF PERSONNEL OFFICER.

SITUATIONS VACANT. Reinforced concrete designer-detailers wanted by British Co. in Mombasa (Kenya), Kampala (Uganda), and Dar-es-Salaam (Tanganyika). Candidates should have had at least five years' experience. Salary according to ability and experience. Free air passages, two months' paid home leave by air each 2½ years, bonus and pension schemes. Applications will be treated in strict confidence. Write Box R13/4/55, 95 Bishopsgate, London, E.C.2.

SITUATIONS VACANT. Reinforced concrete designers and detailers required. Permanent position with good prospects. Pension scheme, five-days' week, and luncheon vouchers. Write or telephone for interview. E. J. COOK & CO. (ENGINEERS), LTD., 54 South Side Clapham Common, London, S.W.4. MACaulay 5522.

SITUATIONS VACANT. Consulting structural engineers, Westminster, require first-class designer-draftsman and a detailer experienced in reinforced concrete and/or steel framed buildings and foundations. High salaries and good prospects for suitable applicants. Write in confidence stating age, qualifications, and details of experience. Box 4167, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATIONS VACANT. Reinforced concrete engineers require designers, detailers, and draftsmen at their Keynham (Bristol) office. Vacancies offer opportunity to work on a variety of structures, and salaries will be dependant on age, experience, etc. Previous similar experience an advantage, but consideration will be given to other suitable applicants. Box 4169, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATIONS VACANT. Designer-draftsmen required for London head office of old-established reinforced concrete engineers. Applicants must be familiar with design of reinforced concrete frames and all forms of reinforced concrete floor construction. The post is permanent, progressive, and pensionable. Existing holiday arrangements would be respected. Substantial salary for experienced men. Write Box 4170, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATIONS VACANT. Senior reinforced concrete designers wanted by leading reinforced concrete engineers and contractors. Must be fully conversant with Code of Practice, L.C.C. Bye-Laws, and able to design light-framed structures from estimating stage to final details. Five-days' week. Pension scheme. Progressive position. Starting salary from £900 upwards according to ability. This year's holiday arrangements honoured. Juniors also required, similar conditions. Write Box 4172, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

DESIGNERS

SIMON-CARVES LTD.

have two vacancies for senior designer-draftsmen as follows:

1. The Colliery Equipment Division requires a man with wide experience of the design of skip-winding and mine-car handling equipment. Candidates should have H.N.C. (Mechanical) or equivalent.
2. The Civil Engineering Department requires a structural designer with experience both of heavy reinforced concrete and steelwork in large industrial contracts. Preference will be given to a man with Graduate Membership of one of the Institutions.

Starting salary (up to £1100 a year) will depend on background. The men appointed will have the opportunity of visiting construction sites, and working conditions are good. The posts are pensionable. Please send brief relevant details (quoting ref. CN49) to Staff and Training Division, Simon-Carves, Ltd., Cheadle Heath, Stockport.

SITUATION VACANT. Detailer-draftsman required for varied reinforced concrete work. Permanent, progressive, and superannuated post. 364-hours' week. Alternate Saturdays. Telephone for appointment (Mr. Disney) ROM RIVER CO., LTD., Euston 7814.

SITUATIONS VACANT. THE BRITISH REINFORCED CONCRETE ENGINEERING CO., LTD., have vacancies for reinforced concrete designers and detailers, with some experience, in their Stafford, London, Liverpool, Bristol, Glasgow and Newcastle-upon-Tyne Offices. Staff pension scheme and five-days' week. Apply in writing to CHIEF ENGINEER, Stafford.

SITUATIONS VACANT. Draftsmen-detailers required for London office of consulting engineers. Some drawing office experience in reinforced concrete work essential. 4 days' week, pension scheme, luncheon and sports club. Apply in writing, with full particulars of age, experience, and salary required, to RENDLE, PALMER & TRITTON, 125 Victoria Street, London, S.W.1.

SITUATIONS VACANT. Consulting engineers require civil engineering, structural, and architectural designer-draftsmen for their Manchester office for work of varied character on major industrial development schemes. A non-contributive pension scheme is in operation and generous salaries will be offered to suitable applicants. Reply in first instance, giving age, experience, and when available, to C. S. ALLOTT & SON, North Parade, St. Mary's Parsonage, Manchester, 3.

SITUATIONS VACANT. Consulting engineers require civil engineering, structural, and architectural designer-draftsmen for a major industrial development scheme in the North-East. It is proposed to provide accommodation at an hotel situated on sea front within 7 miles of site. Alternatively, generous subsistence allowance would be allowed. Transport to and from site will be provided. Interviews will be arranged, and generous salaries offered to suitable applicants. Non-contributive pension scheme in operation. Reply in first instance, giving age, experience, and when available, to C. S. ALLOTT & SON, North Parade, St. Mary's Parsonage, Manchester, 3.

QUANTITY SURVEYOR:

Simon-Carves Ltd.

require a senior quantity surveyor capable of dealing on his own initiative with tenders, interim and final accounts for large civil engineering contracts. Working conditions and scope are excellent. This is regarded as a key post and starting salary will be attractive accordingly. There is a pension scheme. Please send brief relevant particulars (quoting ref. CQ58) to Staff & Training Division, Simon-Carves Ltd., Cheadle Heath, Stockport.

SITUATIONS VACANT. Consulting engineers require in Westminster office designer-draftsmen competent in reinforced concrete and/or steelwork. Good salaries, five-days' week, pension scheme. F. R. BULLER & PARTNERS, Dacre House, Dean Farrar Street, London, S.W.1.

SITUATIONS VACANT. Reinforced concrete detailers required for London office. Previous experience in similar capacity necessary. Attractive conditions of employment. Apply in writing, giving brief particulars of education, experience, age, and quoting L.128, to BRAITHWAITE & CO. ENGINEERS, LTD., 14-16 Regent Street, London, S.W.1

SITUATIONS VACANT. Civil engineering designer-detailers are required for varied and interesting work in N.W. London. Permanent pensioned employment. Five-days' week. Staff canteen. Sports club facilities. Apply in writing, stating age, experience, and approximate salary expected, to Personnel Manager (D.1), JOHN LAING & SON, LTD., Building and Civil Engineering Contractors, London, N.W.7.

SUDAN GOVERNMENT

Sudan Railways require an architectural draughtsman for service in the Sudan for the preparation of drawings and designs as required, and instructing subordinate staff in draughtsmanship. Applicants must have technical knowledge of the standard of National Certificate or better, and have had at least three years' training in architect's or consulting civil engineer's office, and wide experience of drawing office work in the preparation of working drawings and details, and be capable of taking out and preparation of specifications and estimates for various types of civil engineering structures, preferably applied to railway or harbour work. Preference will be given to those with experience of reinforced concrete design. Candidates should be between 25 and 40 years of age. Appointment will be on short term contract (with bonus) for up to three years in the salary scale (£E.800 to £E.1350 per annum. A cost-of-living allowance, which is reviewed quarterly, is also payable. Outfit allowance of (£E.50, and free passages on appointment, and annual leave after the first tour. (£E.1 = £1.0.6d.) Further information and application form will be sent on receipt of a postcard only addressed to The Sudan Agent in London, Sudan House, Cleveland Row, St. James's, London, S.W.1, quoting "ARCHITECTURAL DRAUGHTSMAN 1953" and name and address in BLOCK LETTERS.

SUDAN GOVERNMENT

Sudan Railways require a civil engineering draughtsman for service in the Sudan for the preparation of drawings and designs as required, and the instruction of subordinate staff in draughtsmanship. Applicants must be neat, quick, and accurate draughtsmen, with a sound knowledge of design and construction of varied civil engineering structures, preferably allied to railway or harbour work. They should be capable of taking out quantities, and preparing specifications and estimates. Preference will be given to candidates with experience of reinforced concrete design. Age limit 25 to 40 years. Appointment will be on short term contract, (with bonus) for up to three years in the salary scale (£E.800 to £E.1350 per annum. A cost-of-living allowance, which is reviewed quarterly is also payable. Outfit allowance of (£E.50, and free passages on appointment, and annual leave after the first tour. (£E.1 = £1.0.6d.) Further particulars and application form will be sent on receipt of a postcard only addressed to The Sudan Agent in London, Sudan House, Cleveland Row, St. James's, London, S.W.1, quoting "C.E. DRAUGHTSMAN 1953" and name and address in BLOCK LETTERS.

KENT EDUCATION COMMITTEE

MEDWAY COLLEGE OF TECHNOLOGY, HORSTED, CHATHAM

Lecturer in Civil Engineering subjects required to take up duties in September, to teach to the level of B.Sc. Engineering Degree. Subjects include Geology and Soil Mechanics. Applicants must either be graduates of a British University or Corporate Members of the Institution of Civil Engineers.

Salary: Burnham Scale, £965 rising by annual increments of £25 to a maximum of £1,095 per annum.

Application forms from the Registrar, Medway College of Technology, Maidstone Road, Chatham, should be completed and returned as soon as possible.

CIVIL ENGINEER:

A large company with an international market has a managerial opening for a civil engineer. High professional qualifications are required, and candidates should have had wide experience of large-scale contracting. An interest in administration is essential as the handling of a large staff is involved. Salary will depend on experience. It will not be less than £2,500 a year, and offers excellent prospects. The post will be located in the Manchester area. Details of career and qualifications should be addressed to Box 4173, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1. All replies will be acknowledged and treated in confidence.

(Continued on next page)

MISCELLANEOUS ADVERTISEMENTS.

(Continued from previous page.)

TAYLOR WOODROW CONSTRUCTION LTD.

OFFER EXCELLENT OPPORTUNITIES TO TECHNICAL STAFF

SENIOR ENGINEERS at Head Office and on sites. Must have wide practical knowledge of civil engineering construction detail based on contracting experience, and take a keen interest in construction problems. Duties will require detailed knowledge of planning, plant, design, pricing and execution of all kinds of construction work. Applicants must be versatile and have ability to produce rapid and accurate results.

ASSISTANT ENGINEERS who are desirous of gaining experience in the above field, and prepared to work hard to consolidate their future.

STRUCTURAL DESIGNERS, SOIL MECHANICS and ENGINEERS with specialised practical experience of chemistry and physics testing. The right men will have progressive and remunerative positions. Write giving full details, which will be treated confidentially, to M.D. Engineer, Ruiship Road, Southall, Middlesex.

SITUATIONS VACANT. Structural designer-draftsman with initiative who sees little scope for the use of this at present are invited to contact THE CONCRETE CO. (Telephone: Wimbledon 1191) for an appointment to discuss interesting and permanent work in congenial surroundings with a young and progressive company.

SITUATION VACANT. Senior structural engineer specialising in design of reinforced concrete structures required by Westminster consulting engineers to work in their Surrey office. The position will be permanent and progressive. A self-contained ground floor flat is available to successful applicant if required. A five-days' week and pension scheme are in operation. Apply, stating experience, salary required, and qualifications, to Box 4166, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATIONS VACANT. Reinforced concrete designers (senior and junior) required by consulting engineers for varied and interesting building frames and industrial structures. Good prospects. Five-days' week. Lunch vouchers. Apply with details of experience, etc., to JOHN F. FARQUHARSON & PARTNERS, Chartered Structural Engineers, 34 Queen Anne Street, London, W.1. LANGHAM 6081.

SITUATION VACANT. Reinforced concrete designer-draftsman required by concrete manufacturers in the Midlands. Write, stating age, qualifications, and full details of experience, to Box 4174, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATIONS VACANT. Kingston-on-Thames consultant designer requires reinforced concrete detailers. Excellent salary offered to thoroughly capable men age 20-35. Full particulars of experience, and salary required, to Box 4175, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATION VACANT. Design engineer with good general experience in the design and construction of civil engineering work, particularly in reinforced concrete, required for the drawing office of a large firm of civil engineering contractors in South Lancashire. Applications should indicate qualifications, experience, and salary required. Apply Box 4176, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATIONS VACANT. Consulting structural engineers require assistants with at least two years' office experience in design and/or detailing steel and reinforced concrete frameworks and foundations, following graduation and National Service. Salary £500-£800 per annum according to age, experience, and qualifications. Apply ANDREWS, KENT & STONE, 60-66 Wardour Street, London, W.1. Telephone: Gerrard 9341.

SITUATION VACANT. Research engineer required to work for the cast concrete industry at the laboratories of the Cement and Concrete Association, Wexham Springs, near Slough, on fundamental and applied research. Applicants should preferably be below 27 years of age with Honours Degree in Engineering. Salary according to qualifications and experience. Opportunities for obtaining higher degrees. Possible assistance in housing. Write with full particulars, to Secretary, B.C.C.F., 105 Uxbridge Road, Ealing, W.5.

LONDON COUNTY COUNCIL

ARCHITECT DEPARTMENT

Vacancies in the Structural Engineering Division for Resident Engineers (salary up to £945). Candidates should have B.Sc., A.M.I.C.E., or A.M.I.Struct.E., preferably with experience in supervision of reinforced concrete and/or steel-framed structures on the site, although those with adequate knowledge and experience of design alone will also be considered. Application forms, returnable by 20th August, 1955, from Architect, (AR/EK/RE/4), The County Hall, S.E.1. (1109).

RETTENDON ROOFING TILE WORKS, RETTENDON, ESSEX

Chelmsford 7 miles, Romford 19 miles, Southend 13 miles.

FREEHOLD PREMISES

SUITABLE FOR MAKING

CONCRETE PRODUCTS

comprising

Extensive ranges of brick, concrete, and timber with corrugated-iron and asbestos roofs, DRYING SHEDS, having a total covered area of

approximately 36,000 square feet

and site area of 25 acres, with foreman's house, being eminently suitable for the manufacture of concrete products.

For Sale by Auction

on

Friday, 16th September, 1955

at 4 p.m.

at Chelmsford Corn Exchange, Chelmsford.

Full particulars from the Auctioneers, Messrs. Ofin and Rumsey, Chartered Surveyors, Rochford, Essex (Tel. Rochford 56111), and at 13 King Edward Avenue, Chelmsford (Tel. Chelmsford 2900).

FOR HIRE.


FOR HIRE. Lattice steel erection masts (light and heavy), 30 ft. to 150 ft. high, for immediate hire. BELL-MAN'S, 21 Hobart House, Grosvenor Place, London, S.W.1.

FOR SALE.

FOR SALE. Tinplates, tubes, steel strips, blanks, angles, etc. Priced stock list on application. E. STEPHENS & SON, LTD., Bath Street, London, E.C.1. Clerkenwell 1731.

FOR SALE. Steel guttering, ironwork, sheet metal work. E. STEPHENS & SON, LTD., Bath Street, London, E.C.1. Clerkenwell 1731.

Bar facts



Besides setting new high standards in tensile and bond strength, the TENTOR BAR possesses two other advantages that are of outstanding importance to all structural engineers engaged on reinforced concrete design.

It is highly economical, often saving at least 15% of the cost of Plain Rounds. No hooks are necessary.

It is backed by a first class service supplying bars in straight cut lengths or bent in accordance with requirements.

YOUR JOB COSTS LESS
AND ALWAYS PROCEEDS
TO PROGRAMME
WHEN YOU SPECIFY
TENTOR BARS

The **TENTOR BAR** *Company Limited*

43, Upper Grosvenor St., London, W.1
Telephone: GROsvenor 8101

Tentor is manufactured by
Guest Keen & Nettlefolds (South Wales) Ltd., Cardiff.
McCall & Co. (Sheffield) Ltd., Templeborough, Sheffield.
The United Steel Companies Ltd., Sheffield.

*Complete technical information
is freely available and will
gladly be sent on request.*



STAFFORD
Head Office
Tel: 444

BRC

DESIGN OFFICES

specialising in Reinforced Concrete work are strategically placed throughout the whole of the British Isles



LONDON
53 Grosvenor Street, W.1
Tel: Grosvenor 8371



BRISTOL
10 Orchard St., 1
Tel: 24455



GLASGOW
25 Newton Place
Charing Cross, C.3
Tel: Douglas 5906



NEWCASTLE
107 New Bridge St., 2
Tel: 28136

LIVERPOOL
Hepworth Chambers
Church Street
Tel: Royal 5375



DUBLIN
52 Fitzwilliam Sq.
Tel: 62039



BRC

*Specialists in
Reinforced Concrete
Design
and Suppliers of
Reinforcement*

THE BRITISH REINFORCED CONCRETE ENGINEERING CO. LTD., STAFFORD
London, Birmingham, Bristol, Leeds, Leicester, Liverpool, Manchester, Newcastle, Cardiff, Glasgow, Dublin, Belfast

M-W.783